

MICROFILMED
JUL 1 1988

GENERAL SUMMARY

LAKE COUNTY
LAK-84-27.17

CALC. BY _____ DATE _____	OHIO FHWA REGION 5 FEDERAL PROJECT	14 31
CHKD. BY _____ DATE _____		

ITEM	SHEET NUMBER										ITEM	QUANT.	UNIT	DESCRIPTION	
	9	10	11	15	16	17	23	24	31						
301				28	63		2					301	93	CU.YD.	BITUMINOUS AGGREGATE BASE, AC-20
304				39	34		17					304	90	CU.YD.	AGGREGATE BASE, AS PER PLAN
305				607	539							305	1146	SQ.YD.	7" CONCRETE BASE
310				130	112							310	242	CU.YD.	SUBBASE, TYPE II, AS PER PLAN
403				54	62		6					403	122	CU.YD.	ASPHALT CONCRETE, AC-20
404				48	74		12					404	134	CU.YD.	ASPHALT CONCRETE, AC-20
404												404	1	CU.YD.	ASPHALT CONCRETE, AC-20 (DRIVEWAYS)
407				102	162		25					407	289	GAL	TACK COAT, AS PER PLAN
609					349		126					609	475	LIN.FT.	ASPHALT CONCRETE CURB, AC-20, STANDARD TYPE 1
609				130	226		88					609	444	LIN.FT.	CURB, STANDARD TYPE 6
SPECIAL				367	949							SPECIAL	1316	SQ.YD.	PAVEMENT PLANING, BITUMINOUS WITHOUT HEATING, 1-3/4" DEPTH
SPECIAL				37	96							SPECIAL	133	SQ.YD.	PATCHING PLANED SURFACES
614												614	.44	MILE	TEMPORARY CENTER LINES, CLASS II
614												614	.32	LIN.FT.	TEMPORARY STOP LINES, CLASS I
621												621	.44	MILE	EDGE LINES
621												621	.22	MILE	CENTER LINES
621												621	30	LIN.FT.	STOP LINES
630												630	44	SQ.FT.	SIGNS, FLAT SHEET
630												630	76	LIN.FT.	GROUND MOUNTED SUPPORTS, No. 3 POST
															MISCELLANEOUS
614				LUMP								614	LUMP		MAINTAINING TRAFFIC
619	LUMP											619	LUMP		FIELD OFFICE
623	LUMP											623	LUMP		CONSTRUCTION LAYOUT STAKES, AS PER PLAN
624	LUMP											624	LUMP		MOBILIZATION, AS PER PLAN