

I:\PROJECTS\LAK86\dgn\gs009.dgn 07-MAY-2002 11:55PM pblayney

REF NO.	SHEET NO.	STATION TO STATION	503	507	507	507	518	521	863	863		202	203	606	606				
			Excavation for Structures	Steel Piles, HP 12x53, Furnished	Steel Piles, HP 12x53, Driven	Steel Points or Shoes	Porous Backfill	Bridge Timber, As Per Plan	Structural Steel, Misc.: Retaining Wall Steel, HP 12x53 Wale	Structural Steel, Misc.: Tiebars and Accessories		Guardrail Removed	Embankment	Guardrail, Type 5A	Guardrail, Type 5, As Per Plan				
			Lump	Lin Ft	Lin Ft	Each	Cu Yd	M BFM	Pound	Pound		Lin Ft	Cu Yd	Lin Ft	Lin Ft				
A-1		23+47.85, 14.54' Rt		14	14	1				115									
A-2		23+70.39, 12.57' Rt		13	13	1				115									
A-3		23+93.24, 11.55' Rt		12	12	1				115									
W-1		From 23+37.28, 15.5' Lt to 24+0352, 14.9' Lt	Lump	120	38	8	25	4.1	3268										
GR-1		From 23+50 Lt to 24+25 Lt										75	20	50	25				
TOTALS CARRIED TO GENERAL SUMMARY			Lump	159	77	11	25	4.1	3268	345		75	20	50	25				

Plan Sheet Sub-Summary

LAK-86-1.75

CALCULATED
CHECKED