

SHEET NUMBER

3	4	7	8	11	14	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
										ROADWAY	
						201	11000	LUMP		CLEARING AND GRUBBING	
				190		202	22900	190	SQ. YD.	APPROACH SLAB REMOVED	
				49		202	32001	49	LIN. FT.	CURB REMOVED, AS PER PLAN	13
				31		202	38000	31	LIN. FT.	GUARDRAIL REMOVED	
				18		202	75000	18	LIN. FT.	FENCE REMOVED	
37						203	12000	37	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
2						203	20000	2	CU. YD.	EMBANKMENT	
				212		203	50000	212	SQ. YD.	SUBGRADE COMPACTION	
				1		606	26500	1	EACH	ANCHOR ASSEMBLY, TYPE T	
				2		607	50902	2	EACH	GATE, TYPE CL, (60")	
				12		607	20000	12	LIN. FT.	FENCE, TYPE CL, (60")	
										EROSION CONTROL	
	28					659	14000	28	SQ. YD.	REPAIR SEEDING AND MULCHING	
	0.10					659	20000	0.10	TON	COMMERCIAL FERTILIZER	
	1					659	35000	1	M. GAL.	WATER	
	560					870	10000	560	SQ. YD.	SEEDING AND MULCHING	
	0.10					870	20000	0.10	TON	COMMERCIAL FERTILIZER	
	1					870	35000	1	M. GAL.	WATER	
	2					870	00100	2	EACH	SOIL ANALYSIS TEST	
	32					870	00300	32	CU. YD.	TOPSOIL	
	0.3					870	30000	0.30	TON	AGRICULTURAL LIME	
	28					870	15000	28	SQ. YD.	INTER-SEEDING	
	112					877	10000	112	SQ. YD.	TEMPORARY SEEDING AND MULCHING	
	200					877	30100	200	LIN. FT.	TEMPORARY PERIMETER FILTER FABRIC FENCE	

GENERAL SUMMARY

LAK-90-1.71

TITLE: 1102-GS1
 PLOT: 1102
 DATE: 11/20/01

CALCULATED
 KAM
 CHECKED
 TEN