

SHEET NUMBER														ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
3	4	7	8	11	14															
																			PAVEMENT	
														254	01000	15	SQ. YD.	PAVEMENT PLANING, BITUMINOUS		
														75	01010	75	SQ. YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE		
														36	20000	36	CU. YD.	AGGREGATE BASE		
														16	10000	16	GAL.	TACK COAT		
														6	14000	6	GAL.	TACK COAT FOR INTERMEDIATE COURSE		
														3	46050	3	CU. YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22		
														7	47020	7	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22		
														50	SPECIAL 45130001	50	LIN. FT.	PRESSURE RELIEF JOINT, TYPE A, AS PER PLAN	4	
														200	611 25001	200	SQ. YD.	REINFORCED CONCRETE APPROACH SLAB, (T = 15"), AS PER PLAN	3	
														49	830 26001	49	LIN. FT.	CURB, TYPE 6, AS PER PLAN	14	
																			TRAFFIC CONTROL	
															1	630 08500	1	EACH	STREET NAME SIGN SUPPORT	
															73.5	630 03100	73.5	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
															1	630 80500	1	EACH	SIGN, DOUBLE FACED, STREET NAME	
															5.5	630 80100	5.5	SQ. FT.	SIGN, FLAT SHEET	
															18.25	630 80102	18.25	SQ. FT.	SIGN, FLAT SHEET, TYPE G	
															6	630 85000	6	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
															6	630 86002	6	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
															0.07	642 00302	0.07	MILE	CENTER LINE, TYPE 2	
															14	642 00502	14	LIN. FT.	STOP LINE, TYPE 2	
																			FOR STRUCTURES GENERAL SUMMARY	20
																			MAINTENANCE OF TRAFFIC	
															50	410 12000	50	CU. YD.	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
															100	614 11100	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
															50	SPECIAL 61412600	50	EACH	REPLACEMENT DRUM	7
															50	614 13000	50	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
															8	614 18601	8	SIGN MNTH	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	8
															2	614 22200	2	MILE	TEMPORARY EDGE LINE, CLASS 1, 740.06, TYPE 1	
															1	616 10000	1	M. GAL.	WATER	
															1	616 20000	1	TON	CALCIUM CHLORIDE	
															200	630 97800	200	SQ. FT.	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	7
																614 11000	LUMP		MAINTAINING TRAFFIC	
																623 10000	LUMP		CONSTRUCTION LAYOUT STAKES	
																624 10000	LUMP		MOBILIZATION	
																806 16010	6	MONTH	FIELD OFFICE, TYPE B	

GENERAL SUMMARY

LAK-90-1.71