

PI.01 SUBMITTED:25 FEB 1999 14:18

1942.TSA.DGN

PLOTTED BY: jgrmoyse  
 PLOTTED FROM PROJECTS: P:\19423\19423tso.dgn

\* - IN PLACE OF LANE LINE

LOCATION AND STATION		828								621	
		LANE ARROWS	LANE LINES	EDGE LINES		CHANNELIZING LINES	TRANSVERSE LINES (WHITE)	STOP LINES	#CRD "ONLY" ON PAVEMENT	RAISED PAVT MRKR. INSTALLATION ONLY	
				WHITE	YELLOW					W	Y
FROM	TO	EACH	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	
RAMP "A"											
6+25.28	24+23		1798	1798	1798	GORE *					
RAMP "B"											
5+79.29 (AHEAD)	25+03		1924	1924	1924						
RAMP "C"											
10+60.81	42+28.41		3168	3168	3168						
RAMP "D"											
4+38.54	11+60		1444	722	722						
11+60	14+70		930	310	310						
14+70	20+62		1184	1184	592				34	2	
20+62	38+78.80		1817	1817	1817						
RAMP "E"											
7+56.15	20+72			1316	1316						
13+84	15+70					271	170				
13+84	15+30			180							
15+70	20+72				502						
15+34		1									
RAMP "F"											
4+84								38			
4+86	7+10	6		224	224	224			4		
7+10	22+16.66			1507	1507						
RAMP "G"											
3+69.70	11+43.98			774	774						
RAMP "G-H"											
5+23	13+69.70	2		1692	1692	100		28	2		
RAMP "H"											
13+69.70	23+76.56			1008	1008						
TOTAL THIS SHEET		9	12265	17624	17354	1187	170	66	6	34 2	
TOTAL SHEET XX			131968	68176	66125	7401	2400	2910		389 22	
TOTAL		9	144233 =27.32 MI	85800 =32.06 MI	83479	8588 =10988 L.F.	2400	3080	66	6 423 24	
ITEM 614-TEMPORARY PAV'T MARKINGS			27.32 MI	32.06 MI.		10988 L.F.		66 L.F.			

RAISED PAVEMENT MARKERS ALONG LANE LINES

LANE LINES = 144233 L.F.  
 CHANNELIZING LINES (USED  
 IN PLACE OF LANE LINES) = 2400 L.F.

TOTAL LENGTH = 146,633 L.F.

LANE LINE RPM'S REQUIRED = 146633/80 = 1833 WHITE  
 RPM'S AT GORES = 423 WHITE  
 = 24 YELLOW

GRAND TOTAL = 2256 WHITE AND 24 YELLOW



CALCULATED  
 CHECKED

PAVEMENT MARKING QUANTITIES

LAK-090/271-01.88 / 00.00