

# PAVEMENT MARKING QUANTITIES

LAKE COUNTY  
LAK-90/271-1.88/0.00

OHIO

FHWA REGION 5

FEDERAL PROJECT

122  
185

PLOT SUBMITTED: 17-SEP-1992 13:48  
PLOT FILENAME: dgn  
PLOTTED BY: jilman  
PLOTTED FROM: c:\dgn\pic05772\05772tsa.dgn

PAVEMENT	LOCATION AND STATION		644						642
			4" LANE LINES	4" EDGE LINES		8" CHANNELIZING LINES	24" TRANSVERSE LINES (WHITE)	24" STOP LINES	CENTER LINE TYPE 2
				WHITE	YELLOW				
	FROM	TO	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	
<b>COST PARTICIPATION NB 1-271</b>									
	120+34.62	126+94.62	660						
	126+94.62	133+54.62	660	660					
	133+54.62	134+64.62(BK)	220	110					
	0+00.20(AH)	52+00	10254	5200	5200	146			
<b>COST PARTICIPATION SB 1-271</b>									
	126+94.62	133+54.62	660	660					
	133+54.62	134+64.62(BK)	220	110					
	0+00.20(AH)	52+00	10400	5200	5200				
	WHITE ROAD							402	
<b>TOTAL COST PARTICIPATION I</b>			23,074	10,400	11,940	146		402	
<b>TOTAL TO GENERAL SUMMARY</b>			4.37 MI	4.23 MI		146		0.08 MI.	
<b>COST PARTICIPATION II EB 1-90</b>									
	147+78.40	160+98.40	1320	660					
	160+98.40	162+08.40(BK)	220	110					
	10+00(AH)	23+92	1984	1292	1292	600			
	23+92	26+25.28	266	233	233	666	416		
	26+25.28	35+79.29	954	954	954				
<b>COST PARTICIPATION NB 1-271</b>									
	52+00	56+54	454	454	454	454			
	56+54	59+00.35	292	246	246	692	439		
	59+00.35	92+40.11	3340	3340	3340				
<b>COST PARTICIPATION EB 1-90</b>									
	92+40.11	98+00	1120	1120	560	560			
	98+00	116+25	3650	1825	1825				
	116+25	120+92	1401	467	467				
	120+92	123+31.85	480	240	240	480	377		
	123+31.85	133+71.60	2080	935	1040	105			
	133+71.60	135+00	257	257	128				
	135+00	141+22	1244	1244	▲ 622	278			
	141+22	160+96	3948	1974	▲ 1974				
	160+96	161+76	240	80	▲ 80				
	161+76	164+54.09	556	278	▲ 278	556	454		
	164+54.09	184+94	4080	1940	▲ 2040	609			
	184+94	187+84	870	290	▲ 290				
	187+84	214+83.73(BK)	5400	2700	▲ 2700				
	222+01.66(AH)	301+82	15960	7980	▲ 7980				
	301+82	308+41	659	659	▲ 659				
	308+41	323+81	1,540		1,430				
<b>COST PARTICIPATION SB 1-271</b>									
	52+00	60+11	1622	811	811				
	60+11	62+68	514	514	257	257			
	62+68	63+67.71	100	100	100				
	63+67.71	88+25	2457	2457	2457				
	88+25	90+63.78	239	239	239	239			
	90+63.78	92+40.11	302	176	176	402	483		
<b>COST PARTICIPATION WB 1-90</b>									
	154+38.40	160+98.40	660		660				
	160+98.40	162+08.40(BK)	220	80	110				
	10+00(AH)	14+38.54(BK)	877	439	439				
	92+40.11	93+90	150	150	150	450	94		
	93+90	109+72	2564	1582	1582	600			
	109+72	113+24	1056	352	352				
	113+24	117+49.69	852	852	709	143			
	117+49.69	135+00	3500	1750	1750				
	135+00	142+17	1434	717	▲ 717				
	142+17	144+24	414	207	▲ 207	414	297		
	144+24	145+32	324	108	▲ 108				
	145+32	214+83.73(BK)	13904	6952	▲ 6952				
	222+01.66(AH)	301+82	15960	7980	▲ 7980				
	301+82	308+41	659	659	▲ 659				
	308+41	323+81	1,540		1,540				

PAVEMENT	LOCATION AND STATION		644								642	
			12" TRANSVERSE LINES (WHITE)	LANE ARROWS	4" LANE LINES	4" EDGE LINES		8" CHANNELIZING LINES	24" TRANSVERSE LINES (WHITE)	24" STOP LINES	WORD "ONLY" ON PAVEMENT	CENTER LINE TYPE 2
						WHITE	YELLOW					
	FROM	TO	LIN. FT.	EACH	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	LIN. FT.
<b>RAMP "A"</b>												
	6+25.28	25+46.12			1921	1921	1921	100				
<b>RAMP "B"</b>												
	5+79.29	26+85.12			2106	2106	2106					
<b>RAMP "C"</b>												
	8+13.64	42+28.41			3415	3415	3415					
<b>RAMP "D"</b>												
	4+38.54	12+65			1653	826	826					
<b>RAMP "E"</b>												
	12+65	18+13.64			1097	549	1097	549				
	18+13.64	38+78.80			2065	2065	2065					
<b>RAMP "F"</b>												
	7+56.15	15+70.50				910	830					
	13+84	15+70.50						444				
	14+98	15+70.50	60									
	15+70.50	20+71.96				502	502					
	15+34			1								
<b>RAMP "G"</b>												
	4+84										38	
	4+86	7+00				214	214	214				
<b>RAMP "H"</b>												
	7+00	22+16.66				1517	1517					
	5+12			2								
	5+53											
	5+94			2							2	
	6+35			2								
	6+76			2								
<b>RAMP "I"</b>												
	3+60.11	11+43.65				784	784					
	9+44	11+43.65										
<b>RAMP "G-H"</b>												
	5+21	13+68.21				1852	1766					
	5+42										28	
	5+44	6+44						100				
	5+74			2								
	6+12										2	
<b>RAMP "H"</b>												
	13+68.21	23+76.56				1008	1008					
<b>CHARDON ROAD</b>												
												492
<b>MAPLE GROVE ROAD</b>												
												658
<b>TOTAL COST PARTICIPATION II</b>			60		113,920	72069	40498	8912	2,560	66	4	1150
<b>▲ TOTAL COST PARTICIPATION III</b>							33,246					
<b>TOTAL TO GENERAL SUMMARY II</b>			60		21.58 MI.	21,32	MI.	8912	2,560	66	4	0.22 MI.
<b>▲ TOTAL TO GENERAL SUMMARY III</b>							6.30 MI.					