



SCALE: 1" = 10' 00" NORTH
EASTBOUND - PLANTING PLAN

FOR PLANT BED PREPARATION & BACK FILL SEE PLANT HOLE & BED PREPARATION IN GENERAL NOTES SHEET 2A (TYPICAL)



EXISTING TREES TO BE SAVED (FOR TREE REMOVAL SEE SHEET 2...)

ESTIMATED QUANTITIES:

ITEM	DESCRIPTION	QUANTITY
GENERAL CONTRACT		
SPECIAL	6' WOOD BENCH	2 EACH
659	SEEDING & MULCHING	725 SQ. YDS.
659	COMMERCIAL FERTILIZER	.07 TONS
660	SODDING, AS PER PLAN	210 SQ. YDS.

PLANT LIST:

KEY	BOTANICAL NAME	SIZE	CONDITION	QUANTITY
UPS	ULMUS PARVIFOLIA	2-2 1/2"	B&B	4
PA	PICEA ABIES	6-8'	B&B	1
PM	PSEUDOTSUGA MENZIESII	6-8'	B&B	5
AL	AMELANCHIER LAEVIS (CLUMP TYPE)	6-8'	B&B	5
TMD	TAXUS MEDIA 'DENSIFORMIS'	18-24"	B&B	31
MP	MYRICA PENNSYLVANICA	18-24"	B&B	28
TMH	TAXUS MEDIA 'HUCKII'	18-24"	B&B	14
VON	VIBURNUM OPULUS 'NANUM'	12-15"	CONT.	23
VPT	VIBURNUM RICATUM TOMENTOSUM 'MARESI'	2-3'	B&B	12
AE	AEGOPDIUM PODOGARIA*	2 1/2"	POTS	1250
VM	VINCA MINOR 'ALBA'	1 YR.	PLATS	5350

*AEGOPDIUM PLANTED 1'-0" ON CENTER
 *VINCA PLANTED 6" ON CENTER