ITEMS I-127: The weight of the steel drive posts furnished for these items shall be 2.00 lbs. per foot in lieu of 1.12 lbs. per foot called for in Supplemental Specification No. I-127.

ITEM I-129: All references to Steel Drive Posts weighing 1.12 lbs. per foot appearing throughout this plan shall be considered to read 2.00 lbs. per foot.

GENERAL SUMMARY

FAI ~~SHEET NUMBER~~

ITEM	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	26	29	32	36	38	FAI TOTALS	NON-FED-PARTICIPATION 24	NON FED PART. TOTALS	ITEM	GRAND TOTAL	UNIT	DESCRIPTION TYPE CODE Y002
																																TRAFFIC SIGNS (CONT)
I-128																								2		2			I-128	2	Ea.	Signs M-24-20 20"X 15"
I-128																					3	4	2	4		13			I-128	13	Ea.	Signs IM-24-20 20"X 15"
I-128																					2	4	2	6		14			I-128	14	Ea.	Signs M-25-20 20"X 15"
I-128																								2		2			I-128	2	Ea.	Signs M-26-20 20"X 15"
~~I-128~~																					~~1~~								~~I-128~~	~~1~~	~~Ea.~~	~~Sign M-31-20 20"X 15"~~
I-128																					2	8	4	8		22			I-128	22	Ea.	Signs IM-29-20 20"X 15"
I-128																								2		2			I-128	2	Ea.	Signs M-29-20 20"X 15"
I-128																								1		1			I-128	1	Ea.	Sign M-21-20 20"X 15"
I-128																						2	1	2		5			I-128	5	Ea.	Signs M-37-24N 24"X 12"
I-128																								1		1			I-128	1	Ea.	Sign M-30-20 20"X 15"
I-128																								1		1			I-128	1	Ea.	Sign M-40-24W 24"X 12"
I-128	1		1			1		1			1		1			1			1	1						9			I-128	9	Ea.	Signs IM-40-36W 36"X 18"
I-128																								1		1			I-128	1	Ea.	Sign M-39-24E 24"X 12"
I-128		1	1				1		1		1		1			1			1							8			I-128	8	Ea.	Signs IM-39-36E 36"X 18"
I-128																						2	1	2		5			I-128	5	Ea.	Signs M-38-24S 24"X 12"
I-128																								2		2			I-128	2	Ea.	Signs IM-29-30 30"X 24"
I-128																					1					1			I-128	1	Ea.	Sign IM-26-20 20"X 15"
I-128							2								2						5	4	11	4		28			I-128	28	Ea.	Signs R-69-60 60"X 48"
I-128																					1			1		2			I-128	2	Ea.	Signs R-1-36 36"X 36"
I-128																					4	4	3	4		15			I-128	15	Ea.	Signs R-1-48 48"X 48"
I-128	1	1	1	1		1	1	1	1		2		1	1		2	2	1		2						19			I-128	19	Ea.	Signs R-4-48 48"X 60"
I-128																					4*	4	4	4		16			I-128	16	Ea.	Sign R-7-48 48"X 60"
I-128																					3	4	3	4		14			I-128	14	Ea.	Signs R-10-30 30"X 36"
I-128																					3	4	2	4		13			I-128	13	Ea.	Signs R-13-30 30"X 36"
~~I-128~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~	~~2~~		~~2~~	~~2~~		~~4~~		~~2~~		~~4~~									~~I-128~~	~~36~~	~~Ea.~~	~~Signs R-16-48 48"X 60"~~
I-128																					1	2	1			4			I-128	4	Ea.	Signs R-23-30 30"X 36"
I-128																									4	4			I-128	4	Ea.	Signs R-28-36 36"X 36"
I-128																								2		2			I-128	2	Ea.	Signs R-29-30 30"X 42"
I-128		1	1	1		1			1	1	1	1		1			1	1		1						12			I-128	12	Ea.	Signs R-32-48 48"X 60"
I-128																									4	4			I-128	4	Ea.	Signs R-33-36 36"X 36"
I-128																					1					1			I-128	1	Ea.	Sign R-34-24 24"X 30"
I-128																								3		3			I-128	3	Ea.	Signs R-35-24 24"X 24"
I-128		1	1		2			2	1	1		2		2			2									14			I-128	14	Ea.	Signs R-42-48 48"X 60"
I-128			1	1	1							2														5			I-128	5	Ea.	Signs R-43-48 48"X 60"
I-128		2		2				2		2		2					2									12			I-128	12	Ea.	Signs R-44-48 48"X 60"
I-128																					1					1			I-128	1	Ea.	Sign S-1-96 96"X 18"
I-128																					1					1			I-128	1	Ea.	Sign S-2-96 96"X 18"
I-128							2								2						4	4	11	4		27			I-128	27	Ea.	Signs W-49-48 48"X 48"
I-128																									11	11			I-128	11	Ea.	Signs W-96-36 36"X 36"
																																DELINEATORS
I-127							~~71~~ 65								~~75~~ 69						~~186~~ 183	~~186~~ 174	~~278~~ 265	~~201~~ 189		943			I-127	~~997~~ 943	Ea.	Post Mounted Delineators Type C2, as per plan *
I-127							2								2						4	4	4	4		20			I-127	20	Ea.	Post Mounted Delineators Type C3, as per plan *
I-127																					6		8			14			I-127	14	Ea.	Bracket Mounted Delineators Type C2
~~I-127~~																					~~6~~		~~7~~						~~I-127~~	~~13~~	~~Ea.~~	~~Post Mounted Double Face Delineators Type C2, as per plan *~~
																																SIGN SUPPORTS
I-129	~~27~~ 14	~~54~~ 41	~~56~~ 41	~~47~~ 33	~~33~~ 20	~~34~~ 21	~~50~~ 36	~~54~~ 41	~~41~~ 27	~~40~~ 27	~~46~~ 35	47	~~36~~ 21	~~40~~ 27	22	~~56~~ 28	47	~~27~~ 14	13	~~58~~ 27	~~307~~ 283	~~363~~ 367	~~287~~ 302	~~487~~ 440	76	2050			I-129	~~2322~~ 2050	Lin.Ft.	Steel Drive Posts 2.00 lb. per foot *
I-129																					~~316~~ 269	~~582~~ 506	~~308~~ 265	~~732~~ 646	215	1901			I-129	~~2160~~ 1901	Lin.Ft.	Steel Drive Posts 3.00 lb. per foot
I-129																					28			91		119			I-129	119	Lin.Ft.	Steel Drive Posts 4.00 lb. per foot
I-129	~~74~~ 37	~~148~~ 111	~~147~~ 110	~~130~~ 93	~~215~~ 176	~~151~~ 114	~~325~~ 288	~~148~~ 111	~~111~~ 74	~~111~~ 74	~~129~~ 92	130	~~92~~ 55	~~165~~ 128	70	~~201~~ 127	188	~~74~~ 37	36	~~260~~ 186	~~386~~ 442	~~350~~ 424	~~578~~ 652	~~350~~ 424		4179			I-129	~~4567~~ 4179	Lin.Ft.	Structural Supports 8lb. Beam, As Per Plan
I-129		43	129	43		135	178	135	92	43	141		43	43	86	43	43	43								1240			I-129	1240	Lin.Ft.	Structural Supports, Steel Beam 10B17
I-129	55	110	47	47		53	53	53	53	53	57		110					55	112	57						915			I-129	915	Lin. Ft.	Structural Supports, Steel Beam 12B22
I-129													57	59	59	114	59									348			I-129	348	Lin. Ft.	Structural Supports, Steel Beam 12WF27
I-129																				*					2	2	1	1	I-129	3	Ea.	Overhead Sign Supports I-129 No. 8.2 Design 1, 50' Span
I-129																					1					1			I-129	1	Ea.	Overhead Sign Support I-129 No. 8.1 Design 2, 70' Span
I-129																					1			2		3			I-129	3	Ea.	Overhead Sign Supports I-129 No. 8.1 Design 1, 60' Span
I-129																							4			4			I-129	4	Ea.	Overhead Sign Supports I-129 No. 8.3 Design 2, 80' Span
I-129																							1			1			I-129	1	Ea.	Overhead Sign Support I-129 No. 8.2 Design 1, 70' Span
I-129																							1			1			I-129	1	Ea.	Overhead Sign Support I-129 No. 1.06, 7' Arm
I-129																							1			1			I-129	1	Ea.	Overhead Sign Support I-129 No. 8.2 Design 3, 90' Span
I-129																							1			1			I-129	1	Ea.	Overhead Sign Support I-129 No. 2.14, 11.5' Arm
																																* See note at top of this sheet
I-129	~~3.2~~ 2.9	~~8.5~~ 8.2	10.41	5.85	1.85	10.41	~~14.0~~ 13.7	10.41	7.96	5.74	~~10.2~~ 9.9	1.1	~~11.0~~ 10.7	6.52	7.9	9.82	6.7	5.40	5.4	~~12.0~~ ~~11.6~~ 4.1	~~17.9~~ 18.4	3.28	~~51.5~~ 52.1	~~17.6~~ 18.2	14.4	2482	7.2	7.2	I-129	~~259.7~~ 255.4	Cu.Yds.	Concrete For Sign Support Foundations
I-15																									2200	2200			I-15	2200	Lin.Ft.	Temporary Guard Rail, as per Plan

REV-4-12-60

Rev. 1-11-60 REV. 2-11-60