

PARTICIPATION  
 I - FEDERAL AND STATE  
 II- 100% STATE

SUMMARY

LAKE COUNTY  
 LAK-90-13.00

ITEM	14	15	16	17	33	36	38	41	58	60	75	77	62	ITEM	GRAND TOTAL	UNIT	DESCRIPTION
																	PAVEMENT
301										165			144	301	309	CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20
301	400													301	400	CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20, AS PER PLAN
304										900				304	900	CU. YD.	AGGREGATE BASE
305								2750						305	2750	SQ. YDS.	8" CONCRETE BASE
305								7979						305	7979	SQ. YDS.	10" CONCRETE BASE
310								2555						310	2555	CU. YDS.	SUBBASE, TYPE II, AS PER PLAN
404						1153								404	1153	CU. YDS.	ASPHALT CONCRETE, AC-20, AS PER PLAN
407							31521							407	31521	GAL.	TACK COAT, AS PER PLAN
448	500				8532									448	9032	CU. YDS.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I, AC-20
609	1050													609	1050	LIN. FT.	ASPHALT CONCRETE CURB, AC-20, STANDARD TYPE I
612									242					612	242	SQ. YDS.	CONCRETE MEDIAN, AS PER PLAN
846					17324									846	17324	CU. YDS.	ASPHALT CONCRETE SURFACE COURSE, TYPE I, AC-20
617								5102						617	5102	CU. YDS.	COMPACTED AGGREGATE
SPECIAL										17325				SPECIAL	17325	SQ. YDS.	FULL DEPTH RIGID PAVEMENT REMOVAL AND RIGID REPLACEMENT
SPECIAL		5700								49850				SPECIAL	55550	LIN. FT.	FULL DEPTH PAVEMENT SAWING
SPECIAL					5852									SPECIAL	5852	CU. YDS.	OPEN GRADED ASPHALT CONCRETE FRICTION COURSE, RUBBERIZED
SPECIAL				37.5										SPECIAL	37.5	L. N. MI.	CRACK SEALING IN COMPOSITE PAVEMENT
SPECIAL		1900												SPECIAL	1900	SQ. YDS.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT
																	EROSION CONTROL
207				50										207	50	LIN. FT.	FILTER FABRIC FENCE
601											30			601	30	SQ. YD.	BAGGED CONCRETE RIPRAP, AS PER PLAN
601												9		601	9	LIN. FT.	PAVED GUTTER, STANDARD TYPE I-2
659								13033						659	13033	SQ. YD.	SEEDING AND MULCHING
659								5.86						659	5.86	TON	AGRICULTURAL LIMING
659								1.17						659	1.17	TON	COMMERCIAL FERTILIZER