


TRAFFIC CONTROL QUANTITIES

(620 - DELINEATORS)

LAKE COUNTY
LAK-90-13.00



STATIONS		SIDE	INTERVAL FT.	FLEXIBLE POST MOUNTED		BRACKET MOUNTED
FROM	TO			TYPE C EACH	TYPE D EACH	TYPE C EACH
280 + 50	360 + 50	EB	400	21		
CROSSOVER	329 + 81	EB			1	
360 + 50	368 + 50	EB	200	4		
373 + 00	379 + 00	EB	300	2		1
383 + 50	395 + 50	EB	200	6		
395 + 50	587 + 95	EB	400	49		1
CROSSOVER	401 + 59	EB			1	
587 + 95	595 + 95	EB	200	4		
CROSSOVER	586 + 87	EB			1	
600 + 45	614 + 45	EB	350	5		
620 + 50	630 + 50	EB	200	6		
630 + 50	730 + 50	EB	400	25		
CROSSOVER	644 + 71	EB			1	
SUBTOTAL MAINLINE EASTBOUND				122	4	2
729 + 95	629 + 95	WB	400	25		1
CROSSOVER	644 + 01	WB			1	
629 + 95	621 + 65	WB	200	5		
616 + 90	604 + 90	WB	400	4		
600 + 90	588 + 90	WB	200	7		
CROSSOVER	586 + 17	WB			1	
588 + 90	388 + 90	WB	400	50		1
CROSSOVER	400 + 89	WB			1	
388 + 90	379 + 70	WB	185	5		
376 + 00	360 + 00	WB	400	5		

STATIONS		SIDE	INTERVAL FT.	FLEXIBLE POST MOUNTED		BRACKET MOUNTED
FROM	TO			TYPE C EACH	TYPE D EACH	TYPE C EACH
355 + 90	339 + 90	WB	200	8		
CROSSOVER	328 + 86	WB			1	
339 + 90	279 + 90	WB	400	15		
SUBTOTAL - MAINLINE WESTBOUND				124	4	2
TOTAL - MAINLINE				246	8	4
TOTAL - RAMPS				117	62	1
TOTAL - PROJECT				363	70	5