

I:\PROJECTS\Pid24145\dgn\24145gga.dgn 06-AUG-2002 11:24AM gnowac

| SHEET NUMBER | | | | PARTICIPATION | | | ITEM | ITEM EXT. | GRAND TOTAL | UNIT | DESCRIPTION | SEE SHEET NO. | CALCULATED G/JN | CHECKED LDH |
|--------------|---|------|------|---------------|--|-----|-------|-----------|-------------|---|-------------|---------------|--------------------|----------------|
| 3 | 4 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | ROADWAY | | | | |
| | | 100 | | | | 203 | 20001 | 100 | CU YD | EMBANKMENT, AS PER PLAN | 3 | | | |
| | | | | | | | | | | EROSION CONTROL | | | | |
| | | | 375 | | | | | | | | | | | |
| | | | 50 | | | 207 | 10000 | 375 | SQ YD | CONSTRUCTION SEEDING AND MULCHING | | | | |
| | | | 300 | | | 207 | 25000 | 50 | FT | INLET PROTECTION | | | | |
| | | | 100 | | | 207 | 30100 | 300 | FT | PERIMETER FILTER FABRIC FENCE | | | | |
| | | | 100 | | | 207 | 30200 | 100 | FT | FILTER FABRIC DITCH CHECK | | | | |
| | | | | | | 207 | 40000 | 100 | FT | SLOPE DRAINS | | | | |
| | | | 100 | | | | | | | | | | | |
| | | | 50 | | | 207 | 50000 | 100 | CU YD | SEDIMENT BASINS AND DAMS | | | | |
| | | | 100 | | | 207 | 55000 | 50 | CU YD | DIKES | | | | |
| | | | 50 | | | 207 | 55500 | 100 | SQ YD | CONSTRUCTION DITCH PROTECTION | | | | |
| | | | 50 | | | 207 | 60000 | 50 | CU YD | SEDIMENT REMOVAL | | | | |
| | | | 50 | | | 207 | 70000 | 50 | CU YD | ROCK CHANNEL PROTECTION TYPE C OR D WITH FILTER | | | | |
| | | | | | | 207 | 70020 | 50 | CU YD | ROCK CHANNEL PROTECTION TYPE C OR D WITHOUT FILTER | | | | |
| | | | 42 | | | | | | | | | | | |
| | | | 750 | | | 659 | 00300 | 42 | CU YD | TOPSOIL | | | | |
| | | | 40 | | | 659 | 10000 | 750 | SQ YD | SEEDING AND MULCHING | | | | |
| | | | | | | 659 | 14000 | 40 | SQ YD | REPAIR SEEDING AND MULCHING | | | | |
| | | | 0.10 | | | | | | | | | | | |
| | | | 0.33 | | | 659 | 20000 | 0.10 | TON | COMMERCIAL FERTILIZER | | | | |
| | | | 7 | | | 659 | 30000 | 0.33 | TON | AGRICULTURAL LIME | | | | |
| | | | | | | 659 | 35000 | 7 | M GAL | WATER | | | | |
| | | | 375 | | | | | | | | | | | |
| | | | | | | 670 | 41000 | 375 | SQ YD | SLOPE EROSION PROTECTION | | | | |
| | | | | | | | | | | DRAINAGE | | | | |
| | | 1362 | | | | 603 | 96551 | 1362 | LIN FT | 72" CONDUIT, TYPE A, FIELD PAVING OF EXISTING PIPE, AS PER PLAN | 3 | | | |
| | | 50 | | | | 603 | 98400 | 50 | SQ YD | CONDUIT, MISC.: STRUCTURAL PLATE | 3 | | | |
| | | 2 | | | | 604 | 35501 | 2 | EACH | MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN | 3 | | | |
| | | 9 | | | | 613 | 41250 | 9 | CU YD | LOW STRENGTH MORTAR BACKFILL (TYPE I) | 3 | | | |
| | | | | | | 614 | 11000 | LUMP | | MAINTAINING TRAFFIC | | | | |
| | | | | | | 619 | 16001 | 3 | MONTH | FIELD OFFICE, TYPE A, AS PER PLAN | 4 | | | |
| | | | | | | 623 | 10000 | LUMP | | CONSTRUCTION LAYOUT STAKES | | | | |
| | | | | | | 624 | 10000 | LUMP | | MOBILIZATION | | | | |

GENERAL SUMMARY

LAK-90-14.69

5
9