

# COMPUTATIONS AND SUB-SUMMARIES

## WEARING COURSE REMOVED

STATIONS				SIDE	LOCATION	WIDTH OF FEATHER & REMOVAL LIN. FT.	LENGTH OF FEATHER LIN. FT.	LENGTH OF REMOVAL FOR FEATHER LIN. FT.	LENGTH OF APPROACH SLAB LIN. FT.	202 WEARING COURSE REMOVED SQ. YDS.
FEATHER		REMOVAL								
BEGIN	END	BEGIN	END							
728 + 50.00	730 + 0.00	728 + 50.00	728 + 87.50	EB	BEGIN PROJECT	39.0	150.0	37.5		162.5
827 + 96.50	830 + 9.00	828 + 21.50	830 + 34.00	EB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
838 + 70.00	841 + 32.00	838 + 95.00	841 + 7.50	EB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
0 + 44.61	1 + 94.61	1 + 57.11	1 + 94.61	EB	END PROJECT	39.0	150.0	37.5		162.5
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - MAINLINE EB										2166.6
728 + 50.00	730 + 0.00	728 + 50.00	729 + 0.00	WB	BEGIN PROJECT	39.0	150.0	37.5		162.5
827 + 50.50	829 + 63.00	827 + 72.25	829 + 88.00	WB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
838 + 72.50	840 + 85.00	838 + 47.50	840 + 60.00	WB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
0 + 44.61	1 + 94.61	1 + 57.11	1 + 94.61	WB	END PROJECT	39.0	137.5	37.5		162.5
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - MAINLINE WB										2166.6
				RAMP						
12 + 30.50	12 + 58.00	12 + 50.50	12 + 58.00	I	S.R. 528	VARIES	27.5	7.5		56.3
13 + 34.10	13 + 61.60	13 + 54.10	13 + 61.60	J	S.R. 528	VARIES	27.5	7.5		20.8
0 + 47.50	0 + 75.00	0 + 67.50	0 + 75.00	JSPR	S.R. 528	VARIES	27.5	7.5		29.2
0 + 12.00	0 + 39.50	0 + 12.00	0 + 19.50	K	S.R. 528	VARIES	27.5	7.5		41.7
0 + 13.00	0 + 40.50	0 + 13.00	0 + 20.50	L	S.R. 528	VARIES	27.5	7.5		40.4
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - RAMPS										188.4
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - MAINLINE										4333.2
TOTAL ITEM 202 - WEARING COURSE REMOVED - PROJECT										4521.6