


COMPUTATIONS AND SUB-SUMMARIES

LAKE COUNTY
LAK-90-21.51



STATIONS		RAMP	LANE LINE	EDGE LINE (WHITE)	EDGE LINE (YELLOW)	CHANNELIZING LINE (WHITE)	STOP LINE	TRANSVERSE LINE (WHITE)	LANE ARROWS
FROM	TO		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH
RAMPS									
1 + 82	4 + 53.07	I		271.1		271.1		375.0	
4 + 53.07	5 + 53.07	I		100.0		100.0			
5 + 53.07	12 + 05.43	I		652.4	652.4				
12 + 05.43	12 + 64	I		76.8	73.4		50.0		1
0 + 00	11 + 91.72	J		1,191.7	1,191.7				
11 + 91.72	12 + 32.8	J		41.1					
12 + 32.8	12 + 61.60	J		28.8	28.8				
12 + 61.60	13 + 61.60	J		100.0		198.6			
13 + 61.60	14 + 49	J		87.4		174.8		99.6	
14 + 49	14 + 98.02	J	49.0	49.0					
0 + 00	0 + 93	J SPUR		77.3	103.0				
0 + 12	0 + 52	K		62.8	51.4		42.0		1
0 + 52	5 + 90.23	K		538.2	538.2				
5 + 90.23	6 + 90.23	K		100.0	100.0				
6 + 90.23	9 + 24	K		233.8		233.8		322.6	
0 + 14	0 + 47.15	L		38.4	61.1				
0 + 47.15	13 + 68.60	L		1,321.4	1,321.4				
SUBTOTAL		RAMPS	49.0	4,970.2	4,121.4	978.3	92.0	797.2	2
TOTAL			83,082.7	86,419.5	85,839.3	2,123.8	92.0	797.2	2
TOTAL (MILES)			15.74	16.37	16.26				
				32.63 MILES					