

GENERAL SUMMARY

CALC. BY: T.J.U.
 DATE: 12/90
 CHKD. BY: D.A.M.
 DATE: 12-90

LAK-90-3.28

OHIO
 F.H.W.A. REGION 5

15
38

SHEET NUMBER										PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION
3		13															
																ROADWAY	
		356										202	23000	356	S.Y.	PAVEMENT REMOVED	
		327										202	30500	327	L.F.	CONCRETE MEDIAN REMOVED	
		574.5										202	38000	574.5	L.F.	GUARDRAIL REMOVED	
		126										203	12000	126	C.Y.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
		13										203	20000	13	C.Y.	EMBANKMENT	
		406										203	50000	406	S.Y.	SUBGRADE COMPACTION	
		6.76										203	60000	6.76	STATION	LINEAR GRADING	
		2008										254	01000	2008	S.Y.	PAVEMENT PLANING, BITUMINOUS	
		525										606	13000	525	L.F.	GUARDRAIL, TYPE 5	
		2										606	35000	2	EA.	BRIDGE TERMINAL ASSEMBLY, TYPE 1	
		2										606	35100	2	EA.	BRIDGE TERMINAL ASSEMBLY, TYPE 2	
		943										608	10000	943	S.F.	4" CONCRETE WALK	
																EROSION CONTROL	
	400											207	10000	400	S.Y.	TEMPORARY SEEDING AND MULCHING	
	16											207	70000	16	EA.	STRAW OR HAY BALES	
		1										601	32200	1	C.Y.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
	2000											659	10000	2000	S.Y.	SEEDING AND MULCHING	
	0.20											659	20000	0.20	TON	COMMERCIAL FERTILIZER	
	4											659	35000	4	M.GAL.	WATER	
																DRAINAGE	
		.21										602	20000	.21	C.Y.	CONCRETE MASONRY	
		80										603	04600	80	L.F.	12" CONDUIT, TYPE C, 707.16	
		96										603	04400	96	L.F.	12" CONDUIT, TYPE B, 706.02	
		2										604	00700	2	EA.	CATCH BASIN NO. 3A WITH 'V' GRATE	
		1										604	04500	1	EA.	CATCH BASIN No. 2-2B	
		80										605	31300	80	L.F.	AGGREGATE DRAIN, TRANSVERSE	