

GENERAL SUMMARY

CALC. BY: JLL
DATE: 12/90
CHKD. BY: D.M.
DATE: 12-90

LAK-90-3.28

OHIO
F.H.W.A. REGION 5

16
38

SHEET NUMBER												PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN REF. SEE SHEET
4	5	7	13	14																
PAVEMENT																				
				50								301	10002	50	C.Y.	BITUMINOUS AGGREGATE BASE, AC-20				
			5	95								310	120001	100	C.Y.	SUBBASE, TYPE I, GRADING A, AS PER PLAN	3			
				12								402	20000	12	C.Y.	ASPHALT CONCRETE, AC-20				
				13								403	20000	13	C.Y.	ASPHALT CONCRETE, AC-20				
				114								404	20000	114	C.Y.	ASPHALT CONCRETE, AC-20				
24				335								407	10000	335	GAL	TACK COAT				
			27									305	13000	27	S.Y.	9" CONCRETE BASE				
			105									609	26000	105	L.F.	CURB, TYPE G				
				130								SPECIAL	45132000	130	L.F.	PRESSURE RELIEF JOINT, TYPE C				
												611	25000	373	S.Y.	REINFORCED CONCRETE APPROACH SLAB (T=15")				
				373								612	42000	109	S.Y.	CONCRETE MEDIAN				
				109								617	10100	12	C.Y.	COMPACTED AGGREGATE, TYPE A				
				12																
MAINTENANCE OF TRAFFIC																				
	30											404	35000	30	C.Y.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC				
	170											614	13300	170	EA.	BARRIER REFLECTOR, TYPE B				
			.38									614	20300	.38	MILE	TEMPORARY LANE LINE, CLASS I, 740.05, TYPE C				
			.37									614	21300	.37	MILE	TEMPORARY CENTER LINE, CLASS I, 740.05, TYPE C				
			1.22									614	22300	1.22	MILE	TEMPORARY EDGE LINE, CLASS I, 740.05, TYPE C				
			1675									614	23600	1675	L.F.	TEMPORARY CHANNELIZING LINE, CLASS I, 740.05, TYPE C				
			110									614	24600	110	L.F.	TEMPORARY DOTTED LINE, CLASS I, 740.05, TYPE C				
			176									614	25600	176	L.F.	TEMPORARY TRANSVERSE LINE, CLASS I, 740.05, TYPE C				
			192									614	26600	192	L.F.	TEMPORARY STOP LINES, CLASS I, 740.05, TYPE C				
			14									614	30600	14	EA.	TEMPORARY LANE ARROWS, CLASS I, 740.05, TYPE C				
	382											615	20000	382	S.Y.	TEMPORARY PAVEMENT, CLASS A				
	280											622	40020	280	L.F.	PORTABLE CONCRETE BARRIER, 32 INCH				
	710											622	90000	710	L.F.	PORTABLE CONCRETE BARRIER, TYPE BRD				
	710											622	40050	710	L.F.	PORTABLE CONCRETE BARRIER, TYPE BRD ANCHORED				
STRUCTURE LAK-90-0328 QUANTITIES, SEE SHEET No. 26																				
TRAFFIC CONTROL QUANTITIES, SEE SHEET No. 20																				
												614	11000	LUMP		MAINTAINING TRAFFIC				
												619	15010	LUMP		FIELD OFFICE, TYPE B				
												623	10000	LUMP		CONSTRUCTION LAYOUT STAKES				
												624	10000	LUMP		MOBILIZATION				