

F.H.W.A. REG.	STATE	PROJECT	
5	OHIO		

35
38

LAK-90-3.28
LAKE COUNTY

TABLE OF SCREED ELEVATIONS			
STATION	A	B	C
26+50	753.89		
+75	754.29		
27+00	754.64	755.16	
+25	755.00	755.54	755.02
+50	755.39	755.89	755.40
+75	755.81	756.26	755.75
28+00	756.20	756.68	756.11
+25	756.55	757.07	756.52
+50	756.87	757.44	756.94
+75	757.23	757.77	757.31
29+00	757.61	758.12	757.65
+25	757.99	758.49	757.98
+50	758.35	758.88	758.35
+75	758.72	759.24	758.74
30+00	759.12	759.60	759.11
+25	759.50	760.00	759.46
+50	759.85	760.38	759.84
+75	760.21	760.74	760.24
31+00	760.60	761.09	760.61
+25	760.97	761.47	760.95
+50	761.32	761.86	761.33
+75	761.70	762.22	761.71
32+00	762.11	762.58	762.08
+25	762.51	762.98	762.44
+50	762.85	763.38	762.82
+75		763.75	763.24
33+00		764.07	763.62
+25			763.95

THE ELEVATIONS SHOWN ABOVE ARE TO THE TOP OF THE CONCRETE DECK AND ARE THOSE WHICH ARE REQUIRED BEFORE THE CONCRETE IS PLACED. PROPER ALLOWANCE HAS BEEN MADE FOR THE DEAD LOAD DEFLECTIONS CAUSED BY THE WEIGHT OF THE CONCRETE DECK.

URS					
					13/16
SCREED ELEVATIONS					
BRIDGE N° LAK-90-0328					
S.R. 91 OVER I-90					
LAKE COUNTY			WILLOUGHBY HILLS		
STA 26+74.51 TO STA 33+04.07					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
JH	JWW		JH	JH	10-17-98