

PLOTTED FROM: \\PROJECTS\BP\129\B23129\ggd.dgn

SHEET NUMBER																		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
9	10	11	12	19	36	37																	
					<b>MAINTENANCE OF TRAFFIC</b>																		
			50															614	11100	50	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
				1														614	12336	1	EACH	TEMPORARY IMPACT ATTENUATOR (UNIDIRECTIONAL)	13
			50															614	13000	50	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
			50															614	13001	50	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	11
																		614	13300	112	EACH	BARRIER REFLECTOR, TYPE B	
																		614	13350	112	EACH	OBJECT MARKER	
																		614	18601	4	SIGN MONTH	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	9
			4															614	20100	5.88	MILE	TEMPORARY LANE LINE, CLASS 1, 642 PAINT	
				5.88														614	22100	10.00	MILE	TEMPORARY EDGE LINE, CLASS 1, 642 PAINT	
				10.00														614	23200	1673	LIN FT	TEMPORARY CHANNELIZING LINE, CLASS 1, 642 PAINT	
				1673														622	40020	5590	LIN FT	PORTABLE CONCRETE BARRIER, 32"	
				5590														630	97800	200	SQ FT	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	12
				200														642	30000	12225	LIN FT	REMOVAL OF PAVEMENT MARKING	
				11500														<b>TRAFFIC CONTROL</b>					
																		621	00200	234	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	
																		625	01500	4	EACH	CABLE SPLICING KIT	
																		625	24320	1522	LIN FT	1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES	
																		625	29002	1512	LIN FT	TRENCH, 24" DEEP	
																		625	30706	2	EACH	PULL BOX, 713.08, 24"	
																		625	32000	2	EACH	GROUND ROD	
																		625	34000	1	EACH	POWER SERVICE	
																		626	00100	14	EACH	BARRIER REFLECTOR, TYPE A	
																		626	00200	4	EACH	BARRIER REFLECTOR, TYPE B	
																		630	07000	90	LIN FT	GROUND MOUNTED SUPPORT, W8X18 BEAM	
																		630	07600	160.5	LIN FT	GROUND MOUNTED SUPPORT, W10X12 BEAM	
																		630	09000	12	EACH	BREAKAWAY BEAM CONNECTION	
																		630	21000	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 10, 28' ARM	
																		630	21000	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 10, 30' ARM	
																		630	80204	326	SQ. FT.	SIGN, EXTRUSHEET, TYPE G	
																		630	84500	12	EACH	GROUND MOUNTED BEAM SUPPORT FOUNDATION	
																		630	84510	2	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
																		630	84900	1	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND DISPOSAL	
																		630	85101	8	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND REERECTION, AS PER PLAN	36
																		630	86100	14	EACH	REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL	
																		828	10000	5.97	MILE	EDGE LINE	
																		828	10100	3.97	MILE	LANE LINE	
																		828	10300	1673	LIN FT	CHANNELIZING LINE	
																		828	10600	350	LIN FT	TRANSVERSE LINE	
																		631	84000	1	EACH	SIGN SERVICE	
																		631	84300	1	EACH	SIGN WIRED	
																		631	85100	1	EACH	DISCONNECT SWITCH, TYPE X	
																		631	87154	2	EACH	BALLAST, TYPE CMRI-175-120, INTEGRAL	
																		631	88000	1	EACH	PHOTOELECTRIC CONTROL	
																		631	89200	2	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC-31.21, WITH 175 WATT LAMP	
																		614	11000		LUMP	MAINTAINING TRAFFIC	
																		623	10001		LUMP	CONSTRUCTION LAYOUT STAKES, AS PER PLAN	4
																		624	10000		LUMP	MOBILIZATION	
																		806	16010	5	MONTH	FIELD OFFICE, TYPE B	4

**GENERAL SUMMARY**

**LAK-90-6.71**