

GUARDRAIL QUANTITIES

LAKE COUNTY
LAK-90-6.71

OHIO
FHWA
REGION 5

13
182

GUARDRAIL QUANTITIES

SHEET NO.	REFERENCE NO.	EXISTING LOCATIONS		PROPOSED LOCATIONS		DIRECTION	SIDE	202		606							622		203	448	
		STATION		STATION				GUARDRAIL REMOVED	GUARDRAIL, TYPE 5	GUARDRAIL TYPE 5A	ANCHOR ASSEMBLY, TYPE E	ANCHOR ASSEMBLY, TYPE B	ANCHOR ASSEMBLY, TYPE T	BRIDGE TERMINAL ASSEMBLY, TYPE 1	BRIDGE TERMINAL ASSEMBLY, TYPE 2	BRIDGE TERMINAL ASSEMBLY, TYPE E	CONCRETE BARRIER, TYPE D	LINEAR GRADING	ASPHALT CONCRETE, AC-20 (LENGTH x 0.037 C.Y. / FT.)		
		FROM	TO	FROM	TO			L.F.	L.F.	L.F.	EA.	EA.	EA.	EA.	EA.	EA.	L.F.	L.F.	C.Y.		
31	1-G	209+00	209+78	209+00	209+80	WB	O.L.	78	67.5				1					83			
	2-G	220+98	224+81	221+00	224+62.5	WB	O.L.	383	337.5				1					368.5			
	3-G	234+78	238+00	234+76.5	238+00	WB	O.L.	322	311					1				326.5			
32	1-G	238+00	241+39	238+00	241+39	WB	O.L.	339	339									339			
	2-G	242+80.20	250+11	242+80.20	250+17.70	WB	O.L.	731	725				1					740.5			
	3-G	248+13	255+41	249+50	263+50	WB	O.L.	728	1375				1					1406			
	4-G	260+59	264+00	262+00	264+00	EB	O.L.	341	187.5				1					203			
33	1-G	264+00	265+13	264+00	266+50	EB	O.L.	113	237.5									253			
120	KIRTLAND RD.																				
	1-G			7+41	7+78.5	SB	LT.	65	62.5									65.5			
	2-G	7+39	7+64	6+39	7+64	NB	RT.	25	112.5									126			
	3-G	12+35.5	12+98.5	12+35.5	13+60.5	SB	LT.	63	112.5				1					126			
	4-G	12+21	12+46	12+21	13+46	NB	RT.	25	112.5				1					126			
23*	S.R. 306																				
	1-G	279+43 S.R. 306	13+98 RAMP "L"	279+43 S.R. 306	13+98 RAMP "L"	SB	LT.	595	600									613.5			
	2-G	279+42 S.R. 306	12+43 RAMP "M"	279+42 S.R. 306	12+46 RAMP "M"	NB	RT.	556	525				1					538.5			
	8-G	274+03.5 S.R. 306	275+16 S.R. 306	273+78.5 S.R. 306	275+16 S.R. 306	SB	LT.	112.5	125									138.5			
	9-G	273+01.5 S.R. 306	275+14 S.R. 306	10+25 RAMP "P"	275+14 S.R. 306	NB	RT.	212.5	212.5									226			
	* FOR ADDITIONAL QUANTITIES SEE SHEET NO. 12																				
121	CHILLICOTHE RD.																				
	1-G	25+15	25+65	24+40	25+65	SB	LT.	50	112.5				1					126			
	2-G	25+63.5	26+13.5	25+76	26+13.5	NB	RT.	50	57.5									71			
	3-G	32+23	32+73	32+23	33+48	SB	LT.	50	112.5				1					126			
	4-G	32+71	33+21	32+71	33+96	NB	RT.	50	112.5				1					126			
122	KING MEMORIAL RD.																				
	1-G	27+20	27+76	26+51	27+76	SB	LT.	56	112.5				1					126			
	2-G	27+04	27+60	26+35	27+60	NB	RT.	56	112.5				1					126			
	3-G	32+27	36+77	32+27	36+77	NB	RT.	450	437.5				1					451			
	4-G	32+42	35+67	32+42	35+67	SB	LT.	325	312.5				1					326			
123	LITTLE MOUNTAIN RD.																				
	1-G	6+82.5	7+32.5	6+07.5	7+32.5	SB	LT.	50	112.5				1					126			
	2-G	6+55	7+05	5+80	7+05	NB	RT.	50	112.5				1					126			
	3-G	12+39	12+94	12+39	13+64	SB	LT.	50	112.5				1					126			
	4-G	12+13	12+63	12+13	13+38	NB	RT.	50	112.5				1					126			
SUB-TOTAL THIS SHEET								5976	7262.5				20		9		20	7661.5	283		
SUB-TOTAL (FROM SHEET 12 OF 179)								12155	7122			4006.75	43		21	25	1	1377.0	11434.5	423	
TOTALS								18131	14384.5			4006.75	63		30	25	1	20	1377.0	19096.0 OR 3.62 MILE	706

T:\DGN\LAK-90\QUANTITY\574GRB.DGN

T:\DGN\LAK-90\QUANTITY\574GRB.DGN