GENERAL SUMMARY

LAKE COUNTY
LAK-90-6.71

OHIO
FHWA REGION 5

19
182

ITEM	SHEET NUMBERS		PARTICIPATION I	PARTICIPATION II	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHT. REF.
	155	156								
									MAINTENANCE OF TRAFFIC	
404		350	350		404	35000	350	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
SPECIAL	500		500		SPECIAL	614-11100	500	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL BAR	
614	30		30		614	12470	30	EACH	WORK ZONE SPEED LIMIT SIGN	
SPECIAL		1000	1000		SPECIAL	614-12500	1000	SQ. FT.	REPLACEMENT SIGN	
SPECIAL		1500	1500		SPECIAL	614-12600	1500	EACH	REPLACEMENT DRUM	
614		1248	1248		614	13300	1248	EACH	BARRIER REFLECTOR, TYPE B	
614	1248		1248		614	13350	1248	EACH	OBJECT MARKER	
614	23.18		23.18		614	20100	23.18	MILE	TEMPORARY LANE LINE, CLASS I, 642 PAINT	
614	1.55		1.55		614	20200	1.55	MILE	TEMPORARY LANE LINE, CLASS I, 740.05, TYPE B	
614	38.94		38.94		614	20400	38.94	MILE	TEMPORARY LANE LINE, CLASS II	
614	51.32		51.32		614	22000	51.32	MILE	TEMPORARY EDGE LINE, CLASS I	
614	49.69		49.69		614	22100	49.69	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
614	2.68		2.68		614	22200	2.68	MILE	TEMPORARY EDGE LINE, CLASS I, 740.05, TYPE B	
614	1.23		1.23		614	23400	1.23	MILE	TEMPORARY CHANNELIZING LINE, CLASS I, 740.05, TYPE B	
614	79		79		614	26000	79	LIN. FT.	TEMPORARY STOP LINE, CLASS I	
616		550	550		616	10000	550	M. GAL	WATER	
616		55	55		616	20000	55	TON	CALCIUM CHLORIDE	
622	31161		31161		622	40020	31161	LIN. FT.	PORTABLE CONCRETE BARRIER, 32"	
									FOR TRAFFIC CONTROL GENERAL SUMMARY SEE SHEET NO. 125 & 126	
									FOR STRUCTURES 20' AND OVER GENERAL SUMMARY SEE SHEET NO. 175	
614					614	11000		LUMP	MAINTAINING TRAFFIC	
619					619	15020		LUMP	FIELD OFFICE, TYPE C	
623					623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
624					624	10000		LUMP	MOBILIZATION	

T:\DGN\LAK-90\GENSUM\5774GGC.DGN