

# GENERAL NOTES

LAKE COUNTY  
LAK-90-6.71

OHIO  
FHWA  
REGION 5

124B  
182

## LOCATIONS

THE FOLLOWING IS A SUMMARY OF MAJOR SUPPORT SECTIONS TO HAVE A PROTECTIVE COATING APPLIED:

SUPPORT NO.	NEW GALVANIZED SECTIONS
15	1 VERT. POLE, 1 ARM
21	1 VERT. POLE, 1 ARM
29	1 VERT. POLE, 1 ARM
44	1 VERT. POLE, 1 ARM
50	1 VERT. POLE, 1 ARM
62	1 VERT. POLE, 1 ARM
65	1 VERT. POLE, 1 ARM
73	1 VERT. POLE, 1 ARM
74	1 VERT. POLE, 1 ARM

THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY TO PERFORM THIS WORK:

ITEM SPECIAL - SURFACE PREPARATION, EXISTING SUPPORT SECTION	6 EACH
ITEM SPECIAL - SURFACE PREPARATION, NEW SUPPORT SECTION	18 EACH
ITEM SPECIAL - COATING, EPOXY PRIME COAT, SUPPORT SECTION	24 EACH
ITEM SPECIAL - COATING, EPOXY INTERMEDIATE COAT, SUPPORT SECTION	24 EACH
ITEM SPECIAL - COATING, URETHANE TOP COAT, SUPPORT SECTION	24 EACH

SUPPORT NO.	EXISTING SECTIONS
115	1 VERT. POLE, 1 ARM
116	1 VERT. POLE, 1 ARM
117	1 VERT. POLE, 1 ARM

## ITEM 632 - LOOP DETECTOR WIRE, TYPE E, AS PER PLAN

SPLICES WITH LOOP DETECTOR LEAD IN CABLE SHALL BE IN ACCORDANCE WITH 632.22 AND SHALL BE INCLUDED WITH THIS ITEM OF WORK.

## ITEM 630 - REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF 630.12, THE CONTRACTOR SHALL REMOVE LUMINAIRES (AND HOUSINGS), BALLASTS (AND HOUSINGS), PHOTOELECTRIC CONTROLS AND SIGN WIRING TO THE DISCONNECT SWITCH AS PER 631.16. REMOVED MATERIALS SHALL BE DISPOSED OF BY THE CONTRACTOR. THE COST OF ALL MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE BID (EACH) FOR ITEM 630 - REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL, AS PER PLAN.

## ITEM 603 - 4" CONDUIT, TYPE E (PULL BOXES)

REFERENCE IS MADE TO STANDARD HL-30.11 FOR DETAILS OF DRAINING PULL BOXES. UNDERDRAINS FOR PULL BOXES SHALL BE USED AS DIRECTED BY THE ENGINEER AND SHALL BE PROVIDED WHERE THE LENGTH REQUIRED FOR A SATISFACTORY OUTLET DOES NOT EXCEED APPROXIMATELY 20 FEET. AN ESTIMATED QUANTITY OF 220 LINEAR FEET OF ITEM 603 - 4" CONDUIT, TYPE E IS INCLUDED IN THE GENERAL SUMMARY FOR THIS PURPOSE.