GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

LAKE COUNTY
LAK-1-6.97

11
277

ITEM	202	203	210	213	265	266	267	268	269	270	271	272	273	274	275	276	277	262	263	Calc.	ITEM NO.	QUAN.	UNIT	DESCRIPTIONS
																					TYPE CODE	7221		
																								DRAINAGE (CONTINUED)
S-1		0.82																			S-1	12.3	C.Y.	Concrete for Structures, Class E
S-1																					S-1	207.3	C.Y.	Concrete for Structures, Class C
S-4																					S-4	9179	Lbs.	Reinforcing Steel
S-27		66																			S-27	216	L.F.	24" Pipe for Roadway Culverts Sec. M-6.6 (b) or M-6.8 (b)
S-27																					S-27	138	L.F.	27" Pipe for Roadway Culverts Sec. M-6.6 (b) or M-6.8 (b)
S-27																					S-27	154	L.F.	30" Pipe for Roadway Culverts Sec. M-6.6 (b) or M-6.8 (b)
S-27																					S-27	1040	L.F.	36" Pipe for Roadway Culverts Sec. M-6.6 (b) or M-6.8 (b)
S-27																					S-27	338	L.F.	48" Pipe for Roadway Culverts Sec. M-6.6 (b)
S-27																					S-27	302	L.F.	45" x 29" Pipe for Roadway Culverts Sec. M-206.6 (b)
S-27																					S-27	80	L.F.	60" x 38" Pipe for Roadway Culverts Sec. M-206.6 (b)
S-27																					S-27	82	L.F.	68" x 43" Pipe for Roadway Culverts Sec. M-206.6 (b)
S-27																					S-27	48	L.F.	83" x 53" Pipe for Roadway Culverts Sec. M-206.6 (b)
S-28																					S-28	286	L.F.	60" Sectional Corrugated Metal Structure Sec. M-6.4 (g) 10-10 gage
S-29																					S-29	8	C.Y.	Drainage of Structures, No. 2 Aggregate
																								ROADWAY
E-1																					E-1	1,043,400	C.Y.	Roadway Excavation, Method B, as per plan
E-1	937	1483	1048	1614																	E-1	171,699	S.Y.	Compacted Subgrade
E-9																					E-9	Lump	Lump	Removal of Trees & Stumps
E-11																					E-11	2357	M-Gal.	Water
E-12	110	116																			E-12	660	L.F.	Pipe Removed, 15" and under, as per plan
E-12																					E-12	30	L.F.	Pipe Removed, over 15", as per plan.
I-8																		10	11		I-8	21	Ea.	Centerline Reference Monuments, as per Plan.
I-15																					I-15	6825	L.F.	Guard Rail, Steel Beam, Std. Type (Deep)
I-15		200	200																		I-15	1337.5	L.F.	Guard Rail, Steel Beam Type (Shallow) or Flexible Steel Plate Tension Type Std. Strength
I-15				192																	I-15	976	L.F.	Guard Rail, Wire Cable Type, 3 Cables or Woven Wire Type, 3 tapes Std. Strength
I-16																					I-16	1	Ea.	Manhole Abandoned
L-6																					L-6	402	Units	Roadside Cleanup
L-9	1808	2928	1887	2943																	L-9	542,056	S.Y.	Seeding & Protecting, as per plan
L-9	.16	.26	.17	.26																1.39	L-9	50.17	Tons	Commercial Fertilizer (12-12-12)
L-10		7																			L-10	14,794	S.Y.	Sodding, as per plan.
L-10		136	32	145																	L-10	694	S.Y.	Sodding for Special Berm & Slope Protection.
M-10																					M-10	3	Tons	Calcium Chloride Furnished & Applied for Maintaining Traffic
T-10																					T-10	150	C.Y.	Traffic Compacted Surface Course For Maintaining Traffic
SS-18					1405	3007	3012	3558	3,006	2986	2983	2789	2984	3030	3008	3005	1830				SS-18	36,603	L.F.	Fence, Type D
I-125																					I-125	13.60	Miles	Edge Lines, 4" Wide
I-125																					I-125	2.55	Miles	Center Lines, 6" Wide
I-127																				181	I-127	181	Ea.	Post Mounted Delineators, Type B1, as per plan
S-15																					S-15	Lump	Lump	Temporary Runaround Road using Class B Pav't. as per plan
Special																					Special	2	Ea.	Interstate and Defense Highway Signs furnished and placed
																								BUILDING REMOVAL
S-24												Lump									S-24	Lump	Lump	Removal of one 1-Story Frame Barn and one 2 Story Frame House, Parcel No. 31-5LA
S-24											Lump										S-24	Lump	Lump	Removal of one Quonset Hut and one Chicken Coop; Parcel No. 31-4 LA
S-24															Lump						S-24	Lump	Lump	Removal of one 1-Story Concrete Block and Frame Dwelling, Parcel No. 31-16LA
S-24																Lump					S-24	Lump	Lump	Removal of one 1-Story Ranch Type House, Parcel No. 31-17 LA

REV. 3 1966