

LOCATION NO. / BRIDGE NO.								GENERAL	ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION
1	2	3	4	5	6	7							
LAK-90-0711	LAK-90-1151	LAK-06-0206	LAK-20-1723	LAK-608-0337									
				876				202	23500	876	SQ YD	ROADWAY	WEARING COURSE REMOVED
				131				407	10000	131	GAL	PAVEMENT	TACK COAT
				30.4				448	50001	30.4	CU YD		ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN
				24.3				448	46020	24.3	CU YD		ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I PG64-28
				876				512	55800	876	SQ YD		TYPE D WATERPROOFING
				3				202	54101	3	EA	TRAFFIC CONTROL	RAISED PAVEMENT MARKER REMOVED FOR STORAGE, AS PER PLAN
				3			3	621	00200	6	EA		RAISED PAVEMENT MARKER, INSTALLATION ONLY
				3			3	621	00300	6	EA		PRISMATIC RETROREFLECTOR
				0.08				828	10000	0.08	MI		EDGE LINE (WHITE)
				0.04				828	10200	0.04	MI		CENTER LINE
			6.7					519	12300	6.7	SQ YD	STRUCTURES	PATCHING CONCRETE BRIDGE DECKS, TYPE B
			41					516	01301	41	LIN FT		ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN
			65					516	11211	65	LIN FT		STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN
2600	2620	2950						SPECIAL	519E12602	8170	SQ FT		LOW PRESSURE EPOXY INJECTING OF DELAMINATED CONCRETE
				0.08				614	22100	0.08	MI	MAINTENANCE OF TRAFFIC	TEMPORARY EDGE LINE, CLASS 1, 642 PAINT
								LUMP	614	11000	LUMP		MAINTAINING TRAFFIC
								LUMP	624	10000	LUMP		MOBILIZATION

● ALL OR A PORTION OF THIS QUANTITY IS SUBJECT TO NON-PERFORMANCE WITHOUT PENALTY TO THE STATE OF OHIO.

GENERAL SUMMARY

LAK-90-07.11/VAR