FOR TYPICAL SECTIONS SEE SHEETS 6 THRU 15

PAVEMENT							203	254	301	304	407	446	446		
							SUBGRADE COMPACTION	1 1/4" PAVEMENT PLANING, BITUMINOUS	8" BITUMINOUS AGGREGATE BASE	3" AGGREGATE BASE AS PER PLAN	TACK COAT 0.1 GAL./SQ. YD.	1 3/4" ASPH. CONCRETE INTERMEDIATE COURSE AS PER PLAN	1 1/2" ASPH. CONCRETE SURFACE COURSE AS PER PLAN		
STREET NAME	STATION TO STATION	LENGTH (FEET)	RESURFACE AREA		PAVEMENT AREA										
			AVE.WIDTH (FEET)	P'MT AREA SQ. YDS.	AVE.WIDTH (FEET)	P'MT AREA SQ. YDS.	SQ. YD.	SQ. YD.	CU.YDS.	CU.YDS.	GAL.	CU.YDS.	CU.YDS.		
SR 84	152+60.00 – 155+00.00	240		*782.1	13	346.7	346.7	782.1	77.0	28.9	78.2	16.9	47.0		
SR 84	155+00.00 – 160+09.00	509		*852.9	17	961.4	961.4	852.9	213.6	80.1	85.3	46.7	75.6		
SR 84	160+09.00 – 160+25.00	16		*29.0		*26.7	26.7	29.0	5.9	2.2	2.9	1.3	2.3		
SR 84	161+95.25 – 162+20.29			*87.6		*44.6	44.6	87.6	9.9	3.7	8.8	2.2	5.5		
SR 84	162+20.29 – 166+80.00	459.71		*1362.7		*937.4	937.4	1362.7	208.3	78.1	136.3	45.6	95.9		
SR 84	166+80.00 – 169+30.00	250	26.5	736.1		*417.2	417.2	736.1	92.7	34.8	73.6	20.3	48.1		
							2734	3851	608	228	385	133	275		

QUANTITIES CARRIED TO GENERAL SUMMARY

* AREA CALCULATED BY COMPUTER

CALCULATED JMZ CHECKED WDB

PAVEMENT SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

COPYRIGHT – DATE: 08-09-01 11:03 , CT CONSULTANTS, INC. H:\CT\97125\SDSK\pavesbsum.dwg