

FOR DRIVEWAY DETAILS SEE SHEET 282

STREET NAME	SHEET NUMBER	REFERENCE NUMBER	CENTERLINE STATION	SIDE	TYPE R or C	EXISTING RIGID DRIVEWAY		PROPOSED DRIVEWAY DIMENSIONS				PROPOSED DRIVEWAY AREAS		203		301		304		448	452				
						AVG. WIDTH x LENGTH	202 PAVEMENT REMOVED SQ. YDS.	APRON AREA AVG. WIDTH x LENGTH (FT. x FT.)	DRIVEWAY THRU SIDEWALK AREA LENGTH x WIDTH	DRIVEWAY AREA LENGTH x WIDTH (FT. x FT.)	DRIVEWAY EXTRA AREA	TOTAL RIGID AREA SQ. YDS.	TOTAL FLEXIBLE OR STONE AREA SQ. YDS.	EMBANKMENT CU. YDS.	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION CU. YDS.	3 3/4" BITUMINOUS AGGREGATE PG. 64-22 CU. YDS.	4 3/4" BITUMINOUS AGGREGATE PG. 64-22 CU. YDS.	4" AGGREGATE BASE CU. YDS.	8" AGGREGATE BASE CU. YDS.	1 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 CU. YDS.	6" PLAIN CONCRETE SQ. YDS.	8" PLAIN CONCRETE SQ. YDS.			
S.R. 615	63	DR-1	15+03	LT.	R	-	-	16 x 13.3*	0	0	55 x 12	24.17	73.33	35.08	6.52	7.64	0	0	0	2.55	24.17	0			
S.R. 615	65	DR-2	20+00	RT.	C	-	-	16 x 15*	0	0	1255 x 16	34.11	2231.11	186.86	78.85	0	294.38	247.90	0	108.45	0	34.11			
S.R. 615	77	DR-3	42+80	RT.	R	-	-	6.5 x 12*	5 x 12*	2 x 12	85 x 12	23.31	113.33	28.89	0	11.81	0	0	3.94	23.31	0				
S.R. 615	77	DR-4	43+09	LT.	R	-	-	6.5 x 12*	5 x 12	2 x 12	59 x 11	21.87	74.88	188.9	0	7.79	0	0	2.6	21.87	0				
S.R. 615	79	DR-5	47+12	LT.	R	-	-	6.5 x 12*	5 x 12	2 x 12	25 x 11	24.59	30.56	0	34.18	0	0	6.79	0	24.59	0				
S.R. 615	79	DR-6	48+47	LT.	R	-	-	6.5 x 12*	5 x 12	2 x 12	15 x 11	25.12	18.33	0	19.64	0	0	4.07	0	25.12	0				
S.R. 615	79	DR-7	49+83	LT.	R	-	-	6.5 x 12*	5 x 12	2 x 12	30 x 11	24.56	36.67	0	20.41	0	0	8.15	0	24.56	0				
S.R. 615	83	DR-8	55+60	LT.	R	-	-	6.5 x 13	5 x 13	2 x 13	33 x 13	27.83	47.67	0	47.27	4.97	0	0	1.66	27.83	0				
S.R. 615	83	DR-9	55+70	RT.	R	-	-	146.87*	80.47*	29.45*	364	28.53	40.44	0	39.61	4.21	0	0	1.40	28.53	0				
S.R. 615	93	DR-10	74+98	LT.	R	-	-	129.7*	67.26*	24.2*	210	24.57	23.33	0	20.86	0	0	5.18	0	24.57	0				
												SUBTOTALS				37	295	248	24						
												TOTALS		440	267	332	272	121	225	34					

R = RESIDENTIAL DRIVEWAY
C = COMMERCIAL DRIVEWAY

* AREAS FOR SKEWED DRIVEWAYS BY COMPUTER CALCULATION

SHEET TOTAL CARRIED TO
GRAND TOTAL ON SHEET

CALCULATED
XXX
CHECKED
XXX

DRIVEWAY SUB-SUMMARY

LAK-IR90/SR615-9.26/1.51

55
393

H:\CT\97125\SDSK\DRVSSUM.DWG - PLOT SCALE = 1:1