

DATE: 10-26-01 - H:\CT97125\SDSK1\TRAFFIC\XLS\97125QNT.XLS PLOT PM-1

LOCATION				PAVEMENT MARKINGS														
SHEET NO.	ROADWAY	FROM STATION	TO STATION	828														
				EDGE LINE (WHITE)	EDGE LINE (YELLOW)	LANE LINE	CHANNELIZING LINE, 8 INCH	CENTER LINE, DOUBLE, SOLID (YELLOW)	CENTER LINE, DOUBLE, SOLID & BROKEN (YELLOW)	CURB MARKING (YELLOW)	24" TRANSVERSE LINE, 12' C/C (YELLOW)	24" TRANSVERSE LINE, 12' C/C (WHITE)	STOP LINE	CROSSWALK LINE	LANE ARROW	ISLAND MARKING (YELLOW)	WORD "ONLY" ON PAVEMENT, 72 INCH	
				MILE	MILE	MILE	LIN. FT.	MILE	MILE	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	SQ. FT.	EACH	
299	S.R. 615 - CENTER ST.	11+75	17+50					0.1089										
300	S.R. 615 - CENTER ST.	17+50	20+00					0.0474										
300	S.R. 615 - CENTER ST.	20+00	24+25					0.0805										
300	S.R. 615 - CENTER ST.	24+25	24+50			0.0047		0.0047										
300	MENTOR HILLS DR.	0+13										22						
300	MENTOR HILLS DR.	0+13	0+53					0.0076										
301	S.R. 615 - CENTER ST.	24+50	26+75			0.0426		0.0426										
301	S.R. 615 - CENTER ST.	26+38										31						
301	S.R. 615 - CENTER ST.	26+75	34+50			0.1468		0.1468										
301	S.R. 615 - CENTER ST.	27+31											45					
301	S.R. 615 - CENTER ST.	27+38											45					
301	S.R. 615 - CENTER ST.	27+43										15						
301	I-90 EB EXIT RAMP "C"	87+50	88+48	0.0186	0.0186		98											1
301	I-90 EB EXIT RAMP "C"	87+56																
301	I-90 EB EXIT RAMP "C"	88+18												2				
301	I-90 EB EXIT RAMP "C"	88+48										36						
301	I-90 EB EXIT RAMP "C"	88+53											39					
301	I-90 EB EXIT RAMP "C"	88+60											45					
301	I-90 EB ENTRANCE RAMP "D"	89+16	90+50	0.0254	0.0254													
302	S.R. 615 - CENTER ST.	34+50	36+95			0.0464		0.0464										
302	S.R. 615 - CENTER ST.	36+95	40+16			0.0608	290	0.0608										
302	S.R. 615 - CENTER ST.	37+46												1				
302	S.R. 615 - CENTER ST.	38+14																1
302	S.R. 615 - CENTER ST.	38+80												1				
302	S.R. 615 - CENTER ST.	39+83												1				
302	S.R. 615 - CENTER ST.	40+16	41+60			0.0545		0.0545		86								
302	S.R. 615 - CENTER ST.	41+60	44+05			0.0928			0.0928									
302	S.R. 615 - CENTER ST.	42+86												1				
302	S.R. 615 - CENTER ST.	43+15												1				
302	S.R. 615 - CENTER ST.	44+00								16								
302	S.R. 615 - CENTER ST.	44+05	45+50			0.0549												
302	I-90 WB ENTRANCE RAMP "B"	89+50	91+70	0.0417	0.0483													
302	I-90 WB ENTRANCE RAMP "B"	91+31											57					
302	I-90 WB ENTRANCE RAMP "B"	91+38											72					
302	I-90 WB EXIT RAMP "A"	89+07	90+50	0.0271	0.0271													
302	I-90 WB EXIT RAMP "A"	89+42												68				
302	I-90 WB EXIT RAMP "A"	89+50												48				
302	I-90 WB EXIT RAMP "A"	89+60										56						
303	S.R. 615 - CENTER ST.	45+50	56+50			0.4167												
303	S.R. 615 - CENTER ST.	46+88								16								
303	S.R. 615 - CENTER ST.	47+38								16								
303	S.R. 615 - CENTER ST.	48+22								16								
303	S.R. 615 - CENTER ST.	48+72								16								
303	S.R. 615 - CENTER ST.	49+59								16								
303	S.R. 615 - CENTER ST.	50+09								16								
303	S.R. 615 - CENTER ST.	55+25								16								
303	S.R. 615 - CENTER ST.	56+00								16								
SUB-TOTALS CARRIED TO SHEET 327				0.1128	0.1194	0.9202	388	0.6002	0.0928	144	86	0	160	419	7	0		2

CALCULATED T.E.B.
CHECKED I.M.H.

S.R. 615
PAVEMENT MARKINGS SUBSUMMARY

LAK - IR90 / SR615-9.26 / 1.51