PAVEMENT MARKINGS

LOCATION				828													
SHEET NO.	ROADWAY	FROM STATION	TO STATION	EDGE LINE (WHITE)	EDGE LINE (YELLOW)	LANE LINE	CHANNELIZING LINE, 8 INCH	CENTER LINE, DOUBLE, SOLID (YELLOW)	CENTER LINE, DOUBLE, SOLID & BROKEN (YELLOW)	CURB MARKING (YELLOW)	24" TRANSVERSE LINE, 12' C/C (YELLOW)	24" TRANSVERSE LINE, 12' C/C (WHITE)	STOP LINE	CROSSWALK LINE	LANE ARROW	ISLAND MARKING (YELLOW)	WORD "ONLY" ON PAVEMENT, 72 INCH
				MILE	MILE	MILE	LIN. FT.	MILE	MILE	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	SQ. FT.	EACH
313	I-90 EB EXIT RAMP "C"	70+00	72+81	0.0532													
313	I-90 EB EXIT RAMP "C"	72+81	75+21	0.0455		0.0455											
313	I-90 EB EXIT RAMP "C"	75+21	78+00	0.0528			558					332					
313	I-90 EB EXIT RAMP "C"	78+00	78+50	0.0095	0.0095												
314	I-90 EB EXIT RAMP "C"	78+50	85+73	0.1369	0.1369												
314	I-90 EB EXIT RAMP "C"	85+73	87+50	0.0335	0.0335		177										
314	I-90 EB EXIT RAMP "C"	86+06													2		
314	I-90 EB EXIT RAMP "C"	86+94													2		
315	I-90 EB ENTRANCE RAMP "D"	90+50	98+00	0.142	0.142												
315	I-90 EB ENTRANCE RAMP "D"	98+00	100+50	0.0934	0.0473												
316	I-90 EB ENTRANCE RAMP "D"	100+50	103+00	0.0947	0.0473												
316	I-90 EB ENTRANCE RAMP "D"	103+00	104+39	0.0527			139										
316	I-90 EB ENTRANCE RAMP "D"	104+39	107+17	0.0527		0.0527											
316	I-90 EB ENTRANCE RAMP "D"	107+17	110+50	0.0631													
317	I-90 EB ENTRANCE RAMP "D"	110+50	115+47	0.0941													
SUB-TOTALS				0.9241	0.4165	0.0982	874	0	0	0	0	332	0	0	4	0	0
SUB-TOTALS CARRIED FROM SHEET 325				0.1128	0.1194	0.9202	388	0.6002	0.0928	144	86	0	160	419	7	0	2
SUB-TOTALS CARRIED FROM SHEET 326				1.5862	0.5114	0.904	1912	0.5971	0	0	626	332	171	492	9	115	3
GRAND TOTAL				3.67		1.92	3174	1.29		144	1376		331	911	20	115	5

CALCULATED T.E.B.

CHECKED I.M.H.

S.R. 615
PAVEMENT MARKINGS SUBSUMMARY

LAK - IR90 / SR615-9.26 / 1.51

DATE: 10-26-01 - H:\CT97125\SDSK\TRAFFIC\XLS\97125QNT.XLS PLOT PM-3