SHEET NUMBER																						ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
			11	12		14		19	20		23	24	25			76B											
																										ROADWAY	
																						201	11000	LUMP		CLEARING AND GRUBBING	
											1691											202	23000	1691	SQ. YD.	PAVEMENT REMOVED	
								12608														202	23500	12608	SQ. YD.	WEARING COURSE REMOVED	
											1475											202	30000	1475	SQ. FT.	WALK REMOVED	
				1000																		202	32000	1000	LIN. FT.	CURB REMOVED	
												18										202	35100	18	LIN. FT.	PIPE REMOVED, 24" AND UNDER	
			200																			202	38000	200	LIN. FT.	GUARDRAIL REMOVED	
												1										202	58000	1	EACH	MANHOLE REMOVED	
												1										202	58200	1	EACH	INLET REMOVED	
												2										202	58500	2	EACH	CATCH BASIN ABANDONED	
																						202	98000	LUMP		REMOVAL MISC.: REMOVAL OF CONCRETE FLOWER PLANTERS	11
						40					39					51						203	12000	130	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
			390																			203	60001	390	STATION	LINEAR GRADING, AS PER PLAN A	11
			2																			203	60001	2	STATION	LINEAR GRADING, AS PER PLAN B	11
								11436	4884													254	01000	119245	SQ. YD.	PAVEMENT PLANING, BITUMINOUS	
								66	197													254	01010	263	SQ. YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE	
			2																			604	38500	2	EACH	MONUMENT ASSEMBLY	
													20									604	39501	20	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	13
			200																			606	13000	200	LIN. FT.	GUARDRAIL, TYPE 5	
											1713											608	10000	1713	SQ. FT.	4" CONCRETE WALK	
											4											608	50000	4	EACH	CURB RAMP, TYPE 1	
											27											608	51000	27	EACH	CURB RAMP, TYPE 2	
											350											608	54000	350	SQ. FT.	CURB RAMP, TYPE 2	
													5									SPECIAL	69050000	5	EACH	MAIL BOX SUPPORT	11
																										EROSION CONTROL	
				2400																		207	10000	2400	SQ. YD.	TEMPORARY SEEDING AND MULCHING	
				200																		207	30000	200	LIN. FT.	FILTER FABRIC FENCE	
				120																		207	70000	120	EACH	STRAW OR HAY BALES	
												1.7										601	32200	1.7	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	
				20000																		659	10000	20000	SQ. YD.	SEEDING AND MULCHING	
				0.50																		659	20000	0.50	TON	COMMERCIAL FERTILIZER	
				5.00																		659	35000	5.00	M. GAL.	WATER	
																174						670	40000	174	SQ.YD.	DITCH EROSION PROTECTION	

CALCULATED EMK
CHECKED ENF

GENERAL SUMMARY

CUYAHOGA COUNTY
LAKE COUNTY
CUY/LAK-91-15.42/0.00

PLOTTED BY: fkonopka
PLOTTED FROM: i:\users\bkruse\pid09864\09864gga.dgn
PLOT SUBMITTED: 09-OCT-1998 09:07
09864GGA.DGN