

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\users\bkruse\p\d\09864\09864gqc.dgn
 PLOT SUBMITTED: 14-OCT-1998 10:04
 09864GQC.DGN

SHEET NUMBER

12 15 25 86 87 88 89

ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
WATERWORK					
638	10800	58	EACH	VALVE BOX ADJUSTED TO GRADE	
TRAFFIC CONTROL					
632	26501	47	EACH	DETECTOR LOOP, AS PER PLAN	86
642	00102	1.00	MILE	EDGE LINE, TYPE 2	
642	00202	7.29	MILE	LANE LINE, TYPE 2	
642	00302	6.20	MILE	CENTER LINE, TYPE 2	
642	00402	3167	LIN FT	CHANNELIZING LINE, TYPE 2	
642	00502	1317	LIN FT	STOP LINE, TYPE 2	
642	00602	4183	LIN FT	CROSSWALK LINE, TYPE 2	
642	00702	972	LIN FT	TRANSVERSE LINE, TYPE 2	
642	00902	160	SQ FT	ISLAND MARKING, TYPE 2	
642	01302	117	EACH	LANE ARROW, TYPE 2	
642	01402	20	EACH	WORD ON PAVEMENT, 72", TYPE 2	
MAINTENANCE OF TRAFFIC					
614	13000	100	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
614	20100	15.20	MILE	TEMPORARY LANE LINE, CLASS I, 642 PAINT	
614	21100	12.95	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
614	22100	3.45	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
614	23200	1000	LIN. FT.	TEMPORARY CHANNELIZING LINE, CLASS I, 642 PAINT	
614	26200	870	LIN. FT.	TEMPORARY STOP LINE, CLASS I, 642 PAINT	
614	27200	2000	LIN. FT.	TEMPORARY CROSSWALK LINE, CLASS I, 642 PAINT	
614	30200	40	EACH	TEMPORARY LANE ARROW, CLASS I, 642 PAINT	
616	10000	100	MGAL.	WATER	
616	20000	10	TON	CALCIUM CHLORIDE	
614	11000	LUMP		MAINTAINING TRAFFIC	
623	10001	LUMP		CONSTRUCTION LAYOUT STAKES, AS PER PLAN	11
624	10000	LUMP		MOBILIZATION	
806	16010	9	MONTH	FIELD OFFICE, TYPE B	
806	26000	9	MONTH	COMPUTER EQUIPMENT FOR FIELD OFFICE	

GENERAL SUMMARY

CUYAHOGA COUNTY
 LAKE COUNTY
 CUY/LAK-91-15.42/0.00