

PLOTTED BY: fkonopka
 PLOTTED FROM: \\users\bkruse\p\d\09864\09864gbf.dgn
 09864GBF.DGN
 PLOT SUBMITTED: 09-OCT-1998 09:09

* BUTT JOINT MEETING EXISTING CONCRETE PAVEMENT

** BUTT JOINT MEETING EXISTING ASPHALT OVERLAY

ROADWAY	LOCATION		LENGTH LIN. FT.	AVE. END WIDTH LIN FT	SURFACE AREA SQ. YD.	202	254	254	407		448	446	
	FROM	TO				WEARING COURSE REMOVED SQ. YD.	PAVEMENT PLANING, BITUMINOUS SQ. YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE SQ. YD.	TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL./S.Y.) GALLON	TACK COAT (0.10 GAL./S.Y.) GALLON	2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, PG64-22 CU. YD.	1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN CU. YD.	2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, PG64-22 CU. YD.
CHARDON RD.	4+95.00 **	5+67.40	72.40	CADD	660.67		660.7		9.9	66.1		37.2	9.7
	6+34.48 **	7+10.00	75.52	CADD	751.77		751.8		10.4	75.2		42.6	10.1
EDDY RD.	3+90.00 **	4+65.88	75.88	CADD	354.02		354.0		7.8	35.4		18.9	7.6
	5+42.75 **	6+38.66	95.91	CADD	529.86		529.9		18.8	53.0		29.2	9.2
GLEN-KYLE LN.	10+28.00 *	10+38.00	10.00	CADD	60.11			30.0		6.0		3.3	
TIMBERLINE DR.	10+28.00 **	10+53.00	25.00	CADD	95.19		95.2		0.6	9.5		5.1	0.6
RAMP C-D	5+30.00	5+38.00	8.00	CADD	103.64		103.6		5.2	10.4		4.3	5.8
	5+38.00 **	5+63.00	25.00	CADD	208.55		208.6		2.7	20.9		11.9	2.6
RAMP B	4+82.00	4+95.00	13.00	CADD	96.12		96.1		4.8	9.6		4.0	5.3
	4+95.00 **	5+20.00	25.00	CADD	129.06		129.1		1.5	12.9		7.4	1.4
RAMP A	20+47.00 **	20+72.00	25.00	CADD	75.00		75.0		0.8	7.5		4.4	0.7
RAMP A (CON.)			25.00	CADD	106.37		106.4		1.4	10.6		6.1	1.3
MAPLEGROVE RD.	4+06.00 **	4+71.00	65.00	CADD	330.42		330.4		5.8	33.0		18.2	5.7
	5+27.00 **	5+92.00	65.00	CADD	303.94		303.9		5.8	30.4		16.6	5.6
RIDGE RD.	119+27.60 **	120+13.95	86.35	CADD	409.84		409.8		6.7	41.0		22.8	6.5
		RIGHT HAND TURN LANE		CADD	88.39		88.4		0.9	8.8		5.1	0.9
	121+02.33 **	121+88.77	86.44	CADD	411.31		411.3		6.8	41.1		22.8	6.6
		RIGHT HAND TURN LANE		CADD	87.63		87.6		1.0	8.8		5.1	0.9
HALLE DR.	9+63.00 *	9+73.00	10.00	CADD	66.72			33.3		6.7		3.7	
COLONIAL BLVD.	9+63.00 *	9+73.00	10.00	CADD	64.89			32.4		6.5		3.6	
ASPENWOOD LN.	10+27.00 *	10+37.00	10.00	CADD	62.22			31.1		6.2		3.5	
OAKTREE DR.	9+63.00 *	9+73.00	10.00	CADD	62.80			31.4		6.3		3.5	
TURTLE TR.	10+27.00 **	10+52.00	25.00	CADD	142.22		142.2		1.7	14.2		7.6	0.9
KAISER CT.	10+27.00 *	10+37.00	10.00	CADD	76.89			38.4		7.7		4.3	
TOTALS							4884.0	196.6	92.6	527.8		291.2	81.4
TOTALS CARRIED TO GENERAL SUMMARY							4884	197	93	528		291	81

ASPHALT QUANTITIES	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">DRAWN</td> <td style="font-size: small;">EMK</td> </tr> <tr> <td style="font-size: small;">CALCULATED</td> <td style="font-size: small;">EMK</td> </tr> <tr> <td style="font-size: small;">CHECKED</td> <td style="font-size: small;">ENF</td> </tr> <tr> <td style="font-size: small;">REVISED</td> <td style="font-size: small;">ENF</td> </tr> </table>	DRAWN	EMK	CALCULATED	EMK	CHECKED	ENF	REVISED	ENF
DRAWN	EMK								
CALCULATED	EMK								
CHECKED	ENF								
REVISED	ENF								
CUYAHOGA/LAKE COUNTY CUY/LAK-91-15.42/00.00									
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">20</td> </tr> <tr> <td style="text-align: center;">104</td> </tr> </table>		20	104						
20									
104									