RECAPITULATION GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT	FISCAL YEAR
2	OHIO	LI-662(8)	

8/59

LAKE COUNTY
LAK-91-2.72

SHEET 9	SHEET 10	SHEET 11	SHEET 12	SHEET 13	SHEET 14	SHEET 15	SHEET 16	SHEET 46	SHEET 6	SUB TOTAL	REF. No.	ITEM	QUANTITY & PARTICIPATION TYPE CODE 6203	TYPE CODE Y005	TYPE CODE Y060	TOTAL QUANTITY	UNIT	DESCRIPTION
																		DRAINAGE (CONT.)
			20							20	47 R	I - 1	20			20	LIN. FT.	6" PIPE - CLASS - J-1
112	336	281	351	294	292	101				1767	48 R	I - 1	1767			1767	LIN. FT.	12" PIPE - CLASS - J-1
						354				354	49 R	I - 1	354			354	LIN. FT.	15" PIPE - CLASS - J-1
					67	195				262	50 R	I - 1	262			262	LIN. FT.	18" PIPE - CLASS - J-1
								16		16	51 R	I - 1	16			16	LIN. FT.	48" PIPE - CLASS - A-1, SEC. M-6.4 (d)
	1.8							2.0		3.8	52 R	I - 2	3.8			3.8	CU. YD.	MASONRY
		2								2	53 R	I - 5	2			2	EACH	6" PIPE SPECIAL, CLASS I-3 (NOT A PAY ITEM IN 1967 SPECS.)
		2								2	54 R	I - 5	2			2	EACH	21" PIPE SPECIAL, CLASS E-1 (NOT A PAY ITEM IN 1967 SPECS.)
		2								2	55 R	I - 5	2			2	EACH	24" PIPE SPECIAL, CLASS E-1 (NOT A PAY ITEM IN 1967 SPECS.)
			1							1	56 R	I - 5	1			1	EACH	36" PIPE SPECIAL, CLASS E-1 (NOT A PAY ITEM IN 1967 SPECS.)
	1		1	2	1					5	57 R	I - 8	5			5	EACH	STANDARD INLET NO. 2-6, MODIFIED AS PER PLAN, Median
1	4	1	4	3	6	3				22	58 R	I - 8	22			22	EACH	STANDARD INLET NO. 2-8, MODIFIED AS PER PLAN, Median
1	2	1	3	4	1	2				14	59 R	I - 8	14			14	EACH	STANDARD INLET NO. 2-10, MODIFIED AS PER PLAN, Median
2	2	7	2	1						14	60 R	I - 8	14			14	EACH	STANDARD INLET NO. 2-12, MODIFIED AS PER PLAN, Median
	2	1			1	1				5	61 R	I - 8	5			5	EACH	STANDARD INLET NO. 2-14, MODIFIED AS PER PLAN, Median
	1				1					2	62 R	I - 8	2			2	EACH	STANDARD INLET NO. 2-16, MODIFIED AS PER PLAN, Median
2	6	5	6	4	1	5				29	63 R	I - 8	29			29	EACH	STANDARD NO. 1 MANHOLE
								1		1	64 R	I - 8	1			1	EACH	STANDARD NO. 1-A MANHOLE, MODIFIED, AS PER PLAN
		3	5							8	65 R	I - 8	8			8	EACH	STANDARD NO. 2-2A CATCH BASIN
		1								1	66 R	I - 8	1			1	EACH	STANDARD NO. 2-2B CATCH BASIN
	15	2								17	67 R	I - 10		17		17	CU. YD.	DUMPED ROCK CHANNEL PROTECTION
						3				3	68 R	I - 16	3			3	EACH	CATCH BASINS ABANDONED
	1	5	2	3						11	69 R	I - 16	11			11	EACH	INLETS ABANDONED
								13.0		13.0	70 R	S - 1	13.0			13.0	CU. YD.	CONCRETE FOR STRUCTURES, CLASS "C"
								1663		1663	71 R	S - 4	1663			1663	LBS.	REINFORCING STEEL
								LUMP		LUMP	72 R	S - 22	LUMP			LUMP	LUMP	REMOVAL OF PORTIONS OF EXISTING STRUCTURE
								30		30	73 R	S-23	30			30	Each	Dowel Holes
																		WATER LINE (100% CITY OF WILLOUGHBY PARTICIPATION)
	6									6	74 R	I - 124			6	6	EACH	SERVICE STOP AND BOX, REMOVED AND RESET TO GRADE
	6									6	75 R	I - 124			6	6	EACH	WATER METER AND BOX, REMOVED AND RESET
1	1		3	3	2	3				13	76 R	I - 124			13	13	EACH	HYDRANT VALVE BOX, RESET TO GRADE
			3	2	1	2				8	77 R	I - 124			8	8	EACH	LINE VALVE BOX, RESET TO GRADE

Revised 6-22-65
Revised 4-17-64 Rev. 3-5-68