# GENERAL SUMMARY

| SHEET NUMBER 7 | 8 | 9 | 10 | 11 | 12 | 13 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 | 34 | 35 | 36 | WILL-OUGH-BY | EAST-LAKE | ITEM | ITEM EXT. | TOTAL | UNIT | DESCRIPTION | AS PER PLAN SHT. NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | PAVEMENT | |
| | 250 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | 79937 | | | | | | | | | | | | | | | | | | | | 50 | 200 | 253 | 01000 | 250 | SQ.YD. | PAVEMENT REPAIR | |
| | | | 4917 | | 975 | | | | | | | | | | | | | | | | | | 12240 | 67697 | 254 | 01000 | 79937 | SQ.YD. | PAVEMENT PLANING, BITUMINOUS | |
| | | | | | 1381 | | | | | | | | | | | | | | | | | | 1641 | 4251 | 301 | 10002 | 5892 | CU.YD. | BITUMINOUS AGGREGATE BASE, AC-20 | |
| | | | | | | | | | | | | | | | | | | | | | | | 69 | 1312 | 310 | 12001 | 1381 | CU.YD. | SUBBASE, TYPE I, GRADING A, AS PER PLAN (SEE SHT 8) | 8 |
| | | | 252 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | 8524 | | | | | | | | | | | | | | | | | | | | 170 | 82 | 403 | 20000 | 252 | CU.YD. | ASPHALT CONCRETE, AC-20 | |
| | | | 8000 | | 1562 | | | | | | | | | | | | | | | | | | 1224 | 7300 | 407 | 10000 | 8524 | GALLON | TACK COAT | |
| | | | 3654 | | | | | | | | | | | | | | | | | | | | 1405 | 8157 | 408 | 10000 | 9562 | GALLON | BITUMINOUS PRIME COAT | |
| | | | | 1836 | | | | | | | | | | | | | | | | | | | 541 | 3113 | 446 | 01400 | 3654 | CU.YD. | ASPHALT CONCRETE SURFACE COURSE, TYPE I, AC-20 | |
| 1000 | | | | | 1288 | | | | | | | | | | | | | | | | | | | 1836 | 448 | 14000 | 1836 | CU.YD. | ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I, AC-20 | |
| | | | | | 2265 | | | | | | | | | | | | | | | | | | 220 | 2068 | 609 | 26000 | 2288 | LIN.FT. | CURB, TYPE G | |
| | | | | 158 | | | | | | | | | | | | | | | | | | | 134 | 2131 | 612 | 42000 | 2265 | SQ.YD. | CONCRETE MEDIAN | |
| | 330 | | | | | | | | | | | | | | | | | | | | | | 38 | 120 | 617 | 10100 | 158 | CU.YD. | COMPACTED AGGREGATE, TYPE A | |
| | | | | | | | | | | | | | | | | | | | | | | | | 380 | 255 | 10100 | 380 | SQ.YD. | FULL DEPTH RIGID PAVEMENT REMOVAL AND RIGID | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | REPLACEMENT, CLASS FS | |
| | 1140 | | | | | | | | | | | | | | | | | | | | | | | 1140 | 259 | 20000 | 1140 | LIN.FT. | FULL DEPTH PAVEMENT SAWING | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | 10 | 812 | 20000 | 10 | TON | PORTLAND CEMENT | |
| 430 | | | | | | | | | | | | | | | | | | | | | | | | 430 | SPECIAL | 45012200 | 430 | LIN.FT. | TRANSVERSE JOINT CLEANING AND SEALING, CLASS III, 705.04 | |
| 430 | | | | | | | | | | | | | | | | | | | | | | | | 430 | SPECIAL | 45012400 | 430 | LIN.FT. | TRANSVERSE JOINT CLEANING AND SEALING, CLASS IV, 705.04 | |
| 870 | | | | | | | | | | | | | | | | | | | | | | | | 870 | SPECIAL | 45012600 | 870 | LIN.FT. | LONGITUDINAL JOINT CLEANING AND SEALING, CLASS V, 705.04 | |
| 1300 | | | | | | | | | | | | | | | | | | | | | | | | 1300 | SPECIAL | 45012800 | 1300 | LIN.FT. | LONGITUDINAL JOINT CLEANING AND SEALING, CLASS VI, 705.04 | |
| | 1300 | | | | | | | | | | | | | | | | | | | | | | | 1300 | SPECIAL | 45014000 | 1300 | LIN.FT. | SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINT, 705.04 | |
| 450 | | | | | | | | | | | | | | | | | | | | | | | | 450 | SPECIAL | 45035000 | 450 | LIN.FT. | CRACK CLEANING AND SEALING, CLASS I, 705.04 | |
| 450 | | | | | | | | | | | | | | | | | | | | | | | | 450 | SPECIAL | 45035500 | 450 | LIN.FT. | CRACK CLEANING AND SEALING, CLASS II, 705.04 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | EROSION CONTROL | |
| | 1700 | | | | | | | | | | | | | | | | | | | | | | 340 | 1360 | 207 | 10000 | 1700 | SQ.YD. | TEMPORARY SEEDING AND MULCHING | |
| | 56 | | | | | | | | | | | | | | | | | | | | | | 11 | 45 | 207 | 70000 | 56 | EACH | STRAW OR HAY BALES | |
| | 8500 | | | | | | | | | | | | | | | | | | | | | | 1700 | 6800 | 659 | 10000 | 8500 | SQ.YD. | SEEDING AND MULCHING | |
| | 450 | | | | | | | | | | | | | | | | | | | | | | 90 | 360 | 659 | 14000 | 450 | SQ.YD. | REPAIR SEEDING AND MULCHING | |
| | 0.9 | | | | | | | | | | | | | | | | | | | | | | 0.18 | 0.72 | 659 | 20000 | 0.9 | TON | COMMERCIAL FERTILIZER | |
| | 3.8 | | | | | | | | | | | | | | | | | | | | | | 1.16 | 2.64 | 659 | 30000 | 3.8 | TON | AGRICULTURAL LIMING | |
| | 22 | | | | | | | | | | | | | | | | | | | | | | 6 | 16 | 659 | 35000 | 22 | M GAL. | WATER | |